

TRANSNET FREIGHT RAIL, a division of

#### TRANSNET SOC LTD

Registration Number 1990/000900/30 [hereinafter referred to as **Transnet**]

REQUEST FOR QUOTATION [RFQ] No BFX/52634

FOR THE SUPPLY, INSTALL, TEST AND COMMISSION 5MW RECTIFIER AND ASSOCIATED EQUIPMENT AT GENEVA SUBSTATION

ISSUE DATE : 19 NOVEMBER 2013

CLOSING DATE : 10 DECEMBER 2013

CLOSING TIME : 10:00

FORMAL BRIEFING : 26 NOVEMBER AT 10:00 - A compulsory pre-Quotation

site meeting and/or briefing session will be conducted at

Geneva substation

## NOTE:

FOR ENQUIRIES REGARDING COLLECTION OF DOCUMENTS, CONTACT GIDEON JOUBERT, TELEPHONE 051 408-2167 OR JAKKIE KOTZE TELEPHONE 051 408-2328, RESPECTIVELY

LAST DATE OF ISSUE - RFQ BFX/52634 WILL ONLY BE ISSUED UNTIL 15:00 ON MONDAY, 25 NOVEMBER 2013

# Section 1 NOTICE TO BIDDERS

Quotations which must be completed as indicated in Section 2 of this RFQ are to be submitted as follows:

METHOD:

Courier

**CLOSING VENUE:** 

The Secretariat

Acquisition Council

Admin Support Office

Tender Box Office No. 2

Real Estate Management Building

Austen Street, Beaconsfield

Kimberley (Contact person: Maggie Pain Tel. 053-838 3341)

#### 1 RESPONSES TO RFQ

Responses to this RFQ [**Quotations**] must not include documents or reference relating to any other quotation or proposal. Any additional conditions must be embodied in an accompanying letter.

## 2 BROAD-BASED BLACK ECONOMIC EMPOWERMENT [B-BBEE]

Transnet fully endorses and supports the Government's Broad-Based Black Economic Empowerment Programme and it would therefore prefer to do business with local business enterprises who share these same values. Transnet will accordingly allow a "preference" to companies who provide a valid B-BBEE Verification Certificate. All procurement transactions will be evaluated accordingly.

#### 2.1 B-BBEE Scorecard and Rating

As prescribed in terms of the Preferential Procurement Policy Framework Act (PPPFA), Act 5 of 2000 and its Regulations, Respondents are to note the following:

- Proposals will be evaluated on price which will be allocated 80 or 90 points and preference which will be allocated 20 or 10 points, dependent on the value of the Services.
- The 80/20 preference point system applies where the acquisition of the Services will be less than R1 000 000.00. However, if the 80/20 preference point system is stipulated in this RFQ and all Bids received exceed R1 000 000.00, the RFQ will be cancelled.
- The 90/10 preference point system applies where acquisition of the Services will exceed R1 000 000.00. However, if the 90/10 preference point system is stipulated in this RFQ and all Bids received are equal to or below R1 000 000.00, the RFQ will be cancelled.
- In this RFQ, Transnet will apply 90/10 preference point system prescribed in the PPPFA.

In compliance with the Government Gazette No 34612, Notice No. 754 dated 23 September 2011, as from 1 October 2011 valid B-BBEE Verification Certificates must be issued by:

- (i) Verification Agencies accredited by the South African National Accreditation System [SANAS]; or
- (ii) Registered Auditors approved by the Independent Regulatory Board of Auditors [IRBA], in accordance with the approval granted by the Department of Trade and Industry.

Enterprises will be rated by such agencies based on the following:

- a) Large Enterprises [i.e. annual turnover greater than R35 million]:
  - Rating level based on all seven elements of the B-BBEE scorecard
- b) Qualifying Small Enterprises QSE [i.e. annual turnover between R5 million and R35 million]:
  - · Rating based on any four of the elements of the B-BBEE scorecard
- c) **Exempted Micro Enterprises EME** [i.e. annual turnover less than R5 million]:

In accordance with B-BBEE Codes of Good Practice [Statement 000, Section 4], any enterprise with an annual total revenue of R 5 million or less qualifies as an EME.

- · Automatic rating of 8-8BEE Level 4 irrespective of race or ownership
- Black ownership greater than 50% or Black Women ownership greater than 50% automatically qualify as B-BBEE Level 3

Sufficient evidence to qualify as an EME would be a certificate (which may be in the form of a letter) from an auditor or accounting officer or a certificate from a Verification Agency accredited by SANAS. The certificate must confirm the company's turnover, black ownership / black female ownership, 8-BBEE status level and validity date.

Respondents are required to furnish proof of the above to Transnet. [i.e. a valid detailed scorecard as stipulated above in respect of Large Enterprises and QSEs, or a valid certificate in respect of EMEs1.

Transnet will accordingly allocate a maximum of 10 [ten] points to the Respondent's final score based on an entity's B-BBEE scorecard rating.

N.B. Failure to submit a B-BBEE certificate, which is valid as at the Closing Date of this RFP, will result in a score of zero being allocated for B-BBEE.

[Refer clause 18 below for Returnable Documents required]

#### 3 COMMUNICATION

- a) Respondents are warned that a response will be liable for disqualification should any attempt be made by a Respondent either directly or indirectly to canvass any officer(s) or employee of Transnet in respect of this RFQ between the closing date and the date of the award of the business.
- b) A Respondent may, however, before the closing date and time, direct any written enquiries relating to the RFQ to the following Transnet employee:

Name:

Gideon Joubert

Email:

Gideon.Joubert@Transnet.net

Respondents may also, at any time after the closing date of the RFQ, communicate with Supply
 Chain Services, Admin Support on any matter relating to its RFQ response:

Telephone

053 838 3341

Email

Maggie.Pain@Transnet.net

#### 4 TAX CLEARANCE

The Respondent's original valid Tax Clearance Certificate must accompany the Quotation. Failure to provide this document with the RFQ submission will result in disqualification.

#### 5 VAT REGISTRATION

The valid VAT registration number must be stated here: \_\_\_\_\_\_ [if applicable].

#### **6 LEGAL COMPLIANCE**

The successful Respondent shall be in full and complete compliance with any and all applicable national and local laws and regulations.

#### 7 CHANGES TO QUOTATIONS

Changes by the Respondent to its submission will not be considered after the closing date and time,

#### 8 PRICING

All prices must be quoted in South African Rand on a fixed price basis, excluding VAT.

#### 9 PRICES SUBJECT TO CONFIRMATION

Prices quoted which are subject to confirmation will not be considered.

#### 10 NEGOTIATIONS

Transnet reserves the right to undertake post-tender negotiations with selected Respondents or any number of short-listed Respondents.

#### 11 BINDING OFFER

Any Quotation furnished pursuant to this Request shall be deemed to be an offer. Any exceptions to this statement must be clearly and specifically indicated.

#### 12 DISCLAIMERS

Transnet is not committed to any course of action as a result of its issuance of this RFQ and/or its receipt of a Quotation in response to it. Please note that Transnet reserves the right to:

- modify the RFQ's goods / service(s) and request Respondents to re-bid on any changes;
- reject any Quotation which does not conform to instructions and specifications which are detailed herein;
- disqualify Quotations submitted after the stated submission deadline;
- not necessarily accept the lowest priced Quotation;
- reject all Quotations, if it so decides;
- place an order in connection with this Quotation at any time after the RFQ's closing date;
- award only a portion of the proposed goods / service/s which are reflected in the scope of this RFQ;
- split the award of the order/s between more than one Supplier/Service Provider; or
- make no award at all.

in addition, transfer reserves the right to exclude any Respondent from the bidding process who has
been convicted of a serious breach of law during the preceding 5 [five] years, including but not limited to
breaches of the Competition Act 89 of 1998. Respondents are required to indicate below whether or not
they have been found guilty of a serious breach of law during the past 5 [five] years:
I/We do hereby certify that <i>I/we</i>
have/have not been found guilty during the preceding 5 [five] years of a serious breach of law,
including but not limited to a breach of the Competition Act, 89 of 1998, by a court of law, tribunal or
other administrative body. The type of breach that the Respondent is required to disclose excludes

Where found guilty of such a serious breach, please disclose:

_	· · · · · · · · · · · · · · · · · · ·	
D	ATE OF BREACH:	
F	urthermore, I/we acknowledge that Transnet SOC L	td reserves the right to exclude any Respond
	om the bidding process, should that person or entity ibunal or regulatory obligation.	have been found guilty of a serious breach of I
13 EVA	LUATION CRITERIA	
	ransnet will utilise the following criteria [not necess	arily in this order1 in choosing a Supplier/Sen
	rovider, if so required:	, , , , , , , , , , , , , , , , , , , ,
•	Administrative responsiveness - Completenes	ss of response and returnable documents
•	Substantive responsiveness - Prequalification	,
	materially complies with the scope and/or specific	ation given
•	Weighted evaluation based on 90/10 preference p	point system as indicated in paragraph 0:
	Pricing and price basis (firm) - whilst not the	. anto fachou fou consideration, governatitiva autai
	- Fricing and price basis [mm] - whilst not the	e sole factor for consideration, competitive prici
	and overall level of unconditional discounts <sup>1</sup>	
	<ul> <li>and overall level of unconditional discounts<sup>1</sup></li> <li>B-BBEE status of company</li> </ul>	will be critical
	<ul> <li>and overall level of unconditional discounts<sup>1</sup></li> <li>B-BBEE status of company</li> <li>Preference points will be awarded to a bidder for</li> </ul>	will be critical
	and overall level of unconditional discounts <sup>1</sup> - B-BBEE status of company  Preference points will be awarded to a bidder for in accordance with the table below:	will be critical or attaining the B-BBEE status level of contribute
	and overall level of unconditional discounts <sup>1</sup> - B-BBEE status of company  Preference points will be awarded to a bidder for in accordance with the table below:	will be critical
	and overall level of unconditional discounts <sup>1</sup> - B-BBEE status of company  Preference points will be awarded to a bidder for in accordance with the table below:	will be critical or attaining the B-BBEE status level of contribute
	and overall level of unconditional discounts <sup>1</sup> - B-BBEE status of company  Preference points will be awarded to a bidder for in accordance with the table below:  B-BBEE Status Level of Contributor	will be critical or attaining the B-BBEE status level of contribution of points (90/10 system)
	and overall level of unconditional discounts <sup>1</sup> - B-BBEE status of company  Preference points will be awarded to a bidder for in accordance with the table below:  B-BBEE Status Level of Contributor  1	will be critical or attaining the B-BBEE status level of contribution Number of points (90/10 system)  10 9 8
	and overall level of unconditional discounts <sup>1</sup> - B-BBEE status of company  Preference points will be awarded to a bidder for in accordance with the table below:  B-BBEE Status Level of Contributor  1 2 3	will be critical or attaining the B-BBEE status level of contribution Number of points (90/10 system)  10 9 8 5
	and overall level of unconditional discounts <sup>1</sup> - B-BBEE status of company  Preference points will be awarded to a bidder for in accordance with the table below:  B-BBEE Status Level of Contributor  1 2 3 4 5	will be critical or attaining the B-BBEE status level of contribution Number of points (90/10 system)  10 9 8 5 4
	and overall level of unconditional discounts <sup>1</sup> - B-BBEE status of company  Preference points will be awarded to a bidder for in accordance with the table below:    B-BBEE Status Level of Contributor   1	will be critical or attaining the B-BBEE status level of contribution Number of points (90/10 system)  10 9 8 5 4 3
	and overall level of unconditional discounts <sup>1</sup> - B-BBEE status of company  Preference points will be awarded to a bidder for in accordance with the table below:  B-BBEE Status Level of Contributor  1 2 3 4 5 6 7	will be critical or attaining the B-BBEE status level of contribution  Number of points (90/10 system)  10 9 8 5 4 3 2
	and overall level of unconditional discounts <sup>1</sup> - B-BBEE status of company  Preference points will be awarded to a bidder for in accordance with the table below:    B-BBEE Status Level of Contributor   1	will be critical or attaining the B-BBEE status level of contribution Number of points (90/10 system)  10 9 8 5 4 3
	and overall level of unconditional discounts <sup>1</sup> - B-BBEE status of company  Preference points will be awarded to a bidder for in accordance with the table below:    B-BBEE Status Level of Contributor   1	will be critical or attaining the B-BBEE status level of contribution Number of points (90/10 system)  10 9 8 5 4 3

## 1

14	VALIDITY PERIOD
	Transnet desires a validity period of 90 [ninety] days from the closing date of this RFQ.
	This RFQ is valid until
15	BANKING DETAILS
	BANK:
	BRANCH NAME / CODE:
	ACCOUNT HOLDER:
	ACCOUNT NUMBER:

Only unconditional discounts will be taken into account during evaluation. A discount which has been offered conditionally will, despite not being taken into account for evaluation purposes, be implemented when payment is effected.

16	COMPANY REGISTRATION
	Registration number of company / C.C.
	Registered name of company / C.C.
17	DISCLOSURE OF PRICES QUOTED
	Respondents must indicate here whether Transnet may disclose their quoted prices and conditions to
	other Respondents:
	YES NO NO
18	RETURNABLE DOCUMENTS

**Returnable Documents** means all the documents, Sections and Annexures, as listed in the tables below.

a) Respondents are required to submit with their Quotations the <u>mandatory Returnable</u>
 <u>Documents</u>, as detailed below.

Failure to provide all these Returnable Documents at the Closing Date and time of this RFQ will result in a Respondent's disqualification. Respondents are therefore urged to ensure that <u>all</u> these Documents are returned with their Quotations.

All Sections, as indicated in the footer of each page, must be signed, stamped and dated by the Respondent. Please confirm submission of these mandatory Returnable Documents by so indicating [Yes or No] in the table below:

Mandatory Returnable Documents	Submitted [Yes or No]
SECTION 2 : Quotation Form	
<ul> <li>Original valid Tax Clearance Certificate [Consortia / Joint Ventures must submit a separate Tax Clearance Certificate for each party]</li> </ul>	
ANNEXURE A: Contractual Obligations	
Form E.4E Transnet (Jan 2004) Safety arrangements and Procedural compliance with the Occupational Health and Safety act (Act 85 of 1993 and applicable regulations	7,333,1
E7/1 (July 1998) Specification for general work and works on, over, under or adjacent to Railway lines and near high voltage equipment Special conditions	

b) In addition to the requirements of section (a) above, Respondents are further required to submit with their Quotations the following <u>essential Returnable Documents</u> as detailed below.

Failure to provide all these Returnable Documents may result in a Respondent's disqualification. Respondents are therefore urged to ensure that <u>all</u> these documents are returned with their Quotations.

All Sections, as indicated in the footer of each page, must be signed, stamped and dated by the Respondent. Please confirm submission of these essential Returnable Documents by so indicating [Yes or No] in the table below:

	Essential Returnable Documents	Submitted [Yes or No]
SE	CTION 1 : Notice to Bidders	
-	Valid B-BBEE Verification Certificate [RSA Large Enterprises and QSEs] Note: failure to provide a valid B-BBEE Verification Certificate at the closing date and time of the tender will result in an automatic score of zero being allocated for B-BBEE scorecard	
_	Valid B-BBEE certificate from auditor, accounting officer or SANAS accredited Verification Agency [RSA EMEs]	
	Note: failure to provide a valid B-BBEE Verification Certificate at the closing date and time of the tender will result in an automatic score of zero being allocated for B-BBEE scorecard	
-	In the case of Joint Ventures, a copy of the Joint Venture Agreement or written confirmation of the intention to enter into a Joint Venture Agreement	
-	SECTION 3 : Standard Terms and Conditions of Contract for the Supply of Services to Transnet	
SE	CTION 4 : Vendor Application Form	
-	Original cancelled cheque or bank verification of banking details	
-	Certified copies of IDs of shareholder/directors/members [as applicable]	
-	Certified copy of Certificate of Incorporation [CM29/CM9 name change]	
_	Certified copy of share certificates [CK1/CK2 if C.C.]	
-	Entity's letterhead	773.110.13
_	Certifled copy of VAT Registration Certificate [RSA entities only]	rooranistravi.
-	Certified copy of valid Company Registration Certificate [if applicable]	
-	A signed letter from Respondent's auditor or accountant confirming most recent annual turnover figures	

c) In addition to the requirements of paragraph a) and b) above, Respondents are further requested to submit with their Proposals the following **additional documents** as detailed below.

Please confirm submission of these additional documents by so indicating [Yes or No] in the table below:

-	ADDITIONAL DOCUMENTS	MITTED [Yes or No]
Ī	Letter of Good Standing	

# Section 2 QUOTATION FORM

Me		
7 • • · · · · · · · · · · · · · · · · ·	 	<del></del>

hereby offer to supply the goods/services at the prices quoted in the Price Schedule below, in accordance with the conditions related thereto.

I/We agree to be bound by those terms and conditions in:

- the Standard Terms and Conditions for the Supply of Goods or Services to Transnet [Section 3 hereof];
   and
- any other standard or special conditions mentioned and/or embodied in this Request for Quotation.

I/We accept that unless Transnet should otherwise decide and so inform me/us, this Quotation [and, if any, its covering letter and any subsequent exchange of correspondence], together with Transnet's acceptance thereof shall constitute a binding contract between Transnet and me/us.

I/We further agree that if, after I/we have been notified of the acceptance of my/our Quotation, I/we fail to deliver the said goods/service/s within the delivery lead-time quoted, Transnet may, without prejudice to any other legal remedy which it may have, cancel the order and recover from me/us any expenses incurred by Transnet in calling for Quotations afresh and/or having to accept any less favourable offer.

## Price Schedule

I/We quote as follows for the service required, on a "delivered nominated destination" basis, excluding VAT:

Item	Description	Unit	Qty	Rate	Price
aavidi x	GENEVA 3 kV Substation				
1	Dismantle, remove and transport all old equipment from site to Bloemfontein depot.	sum	1	R	R
2	Supply Aluminium busbars (50x25mm²) from Main Transformer secondary bushings to wall bushings with flexible connectors.	sum	1	R	R
3	Supply all Aluminium busbars (50x25mm²) from wall bushings to rectifier	sum	1	R	R
4	Supply Aluminium busbar (127x12.5mm²) from Rectifier to Reactor Coil	sum	1	R	R
5	Supply Aluminium busbar (127x12.5mm²) from Rectifier to the negative busbar	sum	1	R	R
6	Supply Aluminium busbars (127x12.5mm²) from Reactor Coll to Positive Isolator	sum	1	R	R
7	Supply 500mm <sup>2</sup> positive cables from positive isolator to busbar chamber complete with joint and termination kits.	sum	1	R	R
8	Supply and connect all control cables from the substation outdoor yard to the substation indoor building including Auxiliary, track breakers and tele-control cables.	sum	1	R	R
9	Supply complete set of mechanical interlocking keys.	sum	1	R	R
11	Supply AC/DC distribution panel	ea	1	R	R

Data & Construction

12	Connect Wave Filter equipment to the panel	sum	1	R	R
13	Supply DC earth leakage relay with its polycarbonate box and mount outside the panel	ea	1	R	R
14	Supply FP-2004 relays	ea	2	R	R
15	Supply checker plates	sum	1	R	R
17	Supply shunt 4000/50mV	ea	1	R	R
18	Supply, install and relocate the negative bar in the outdoor yard to the rectifier bay with its associated cables complete with shunt	sum	1	R	R
19	SUPPLYAND INSTALL 5 MW Rectifier	ea	1	R	R
20	Modify Rectifier Bay Mesh to accommodate Positive Isolator	sum	1	R	R
21	Supply Positive Isolator complete with fibre optic under voltage relay.	ea	1	R	R
22	Supply HT cable linking wave filter, positive isolator and reactor coil	sum	1	R	R
23	Supply cables for the DC earth leakage system and redo indoor earthing.	sum	1	R	R
24	Supply support steel structure for Secondary Surge Arrestors	sum	1	R	R
25	Supply material and cast foundation for Secondary Surge Arrestors	sum	1	R	R
26	Supply and install AC earth leakage CT	еа	1	R	R
27	Re-do outdoor earth complete and relocate Surge currently to their independent Steel Structure	sum	1	R	R
28	Installation, Testing and Pre-commissioning	sum	1	R	R
39	P's & G's	sum	1	R	R
30	Security	sum	1	R	R
	Total Price for GENEVA (Excl. VAT)	<u> </u>	R	Ba <i>mananan mera<del></del></i>	<u>L</u>

otal Price for GENEVA (Excl. VAT)	R
Delivery Lead-Time from date of purchase orde	r:[days/weeks]

#### **Notes to Pricing:**

- a) All Prices must be quoted in South African Rand, exclusive of VAT
- b) To facilitate like-for-like comparison bidders must submit pricing strictly in accordance with this price schedule and not utilise a different format. Deviation from this pricing schedule could result in a bid being disqualified.
- c) Please note that should you have offered a discounted price(s), Transnet will only consider such price discount(s) in the final evaluation stage if offered on an unconditional basis.



#### Section 3

#### STANDARD TERMS AND CONDITIONS FOR THE SUPPLY OF GOODS OR SERVICES TO TRANSNET

A Supplier/Service Provider shall be obliged to adhere to the Standard Terms and Conditions for the Supply of Goods and Services to Transnet as expressed hereunder. Should the Respondent find any condition(s) unacceptable, it should indicate which condition(s) is/are unacceptable and offer an alternative(s). A Quotation submitted by a Respondent will be subjected to review and acceptance or rejection of its proposed contractual terms and conditions by Transnet's Legal Counsel, prior to consideration for an award of business.

#### 1 SOLE AGREEMENT

Unless otherwise agreed in writing, these terms [**Terms** and each **Term**] and Transnet's purchase order(s) [**Order** or **Orders**] represent the only conditions upon which Transnet SOC Ltd [**Transnet**] procures goods [**the Goods**] or services [**the Services**] specified in the Order from the person to whom the Order is addressed [**the Supplier/Service Provider**]. Transnet does not accept any other conditions which the Supplier/Service Provider may specify, unless otherwise agreed to by Transnet in writing. In the event of any inconsistency between these Terms and any Order, these Terms shall take precedence.

#### 2 CONFORMITY WITH ORDER

Goods/Services shall conform strictly with the Order. The Supplier/Service Provider shall not vary the quantities specified and/or the specification, if any, stipulated in the Order, without the prior written consent of Transnet. The Supplier/Service Provider warrants that the Goods/Services shall be fit for their purpose and of satisfactory quality.

#### 3 DELIVERY AND TITLE

- 3.1 The delivery dates and addresses are those in the Order. Time shall be of the essence in respect of the Supplier's/Service Provider's obligations under the Order.
- 3.2 The Supplier/Service Provider will not be excused for delay in delivery or performance except due to circumstances outside its control and then only subject to the Supplier/Service Provider having notified Transnet in writing on becoming aware of such circumstances. Transnet may terminate an Order, in whole or in part, without incurring any liability to the Supplier/Service Provider if such a delay becomes, in Transnet's absolute opinion, significant.
- 3.3 If on delivery, the Goods/Services do not conform to the Order, Transnet may reject the Goods/Services and the Supplier/Service Provider shall promptly rectify any defects or in Transnet's opinion, supply appropriate replacement Goods/Services at the Supplier's/Service Provider's expense within the specified delivery times, without any liability due by Transnet.

#### 4 PRICE AND PAYMENT

- 4.1 Prices specified in an Order cannot be increased. Payment for the Goods/Services shall be made by Transnet against an original undisputed invoice(s) [a Tax Invoice], supporting documentation and month-end statement from the Supplier/Service Provider. Tax Invoices plus supporting documentation shall be posted to the address shown in the Order.
- 4.2 Payment of the Supplier's/Service Provider's valid Tax Invoice(s) will be made by Transnet in the South African currency and on the terms stated in the Order, the standard payment terms being 30

[thirty] days from date of receipt by Transnet of a month-end statement, unless otherwise agreed to in writing. Transnet shall arrange for payment of such Tax Invoices and any pre-authorised additional expenses incurred, provided that the authorised expenses are supported by acceptable documentary proof of expenditure incurred [where this is available]. Any amounts due in terms of these Terms shall be paid to the Supplier/Service Provider, taking into account any deduction or set-off and bank charges.

#### 5 PROPRIETARY RIGHTS LIABILITY

If any allegations should be made or any claim asserted against Transnet that ownership of, or any act or omission by Transnet in relation to Goods/Services or any written material provided to Transnet relating to any Goods/Services or pursuant to an Order being a violation or infringement of any third party's contractual, industrial, commercial or intellectual property rights including but not limited to any patent, registered design, design right, trade mark, copyright or service mark on any application thereof, the Supplier/Service Provider hereby indemnifies Transnet against and hold it harmless from any and all losses, liabilities, costs, claims, damages and expenses [including any legal fees] arising directly or indirectly from such allegation or claim provided that this indemnity shall not apply where the allegation or claim arises solely as a result of the Supplier/Service Provider following a design or process originated and furnished by Transnet. The Supplier/Service Provider shall either

- a) procure for Transnet the right to continue using the infringing Goods; or
- b) modify or replace the Goods/Services so that they become non-infringing, provided that in both cases the Goods/Services shall continue to meet Transnet's requirements and any specifications stipulated in the Order. Should neither option be possible, the Supplier/Service Provider may remove, with Transnet's prior written consent, such Goods/Services and will pay to Transnet a sum equivalent to the purchase price. If Transnet refuses to give such consent, the Supplier/Service Provider shall have no liability in respect of any continued use of the infringing Goods/Services after Supplier's/Service Provider's prior written request to remove the same.

#### 6 PROPRIETARY INFORMATION

All information which Transnet has divulged or may divulge to the Supplier/Service Provider and any information relating to Transnet's business which may have come into the Supplier's/Service Provider's possession whilst carrying out an Order, and the existence of the Order, shall be treated by the Supplier/Service Provider as confidential information and shall not, without Transnet's prior written consent, be disclosed to any third party, or be used or copied for any purposes other than to perform the Order. This clause does not apply to information which is public knowledge or available from other sources other than by breach of this Term. Upon request by Transnet, the Supplier/Service Provider shall return all materials issued pursuant to the Order and, pending this, shall protect Transnet's rights in any such materials. Such confidential information shall at all material times be the property of Transnet.

### 7 PUBLICITY

The Supplier/Service Provider shall not name Transnet or use its trademarks, service marks [whether registered or not] or Goods in connection with any publicity without Transnet's prior written consent.

#### 8 **TERMINATION OF ORDER**

- Transnet may cancel an Order in whole or in part at any time upon at least 7 [seven] days' written 8.1 notice to the Supplier/Service Provider, or when there is a change in control of the Supplier/Service Provider or the Supplier/Service Provider commits any serious breach or any repeated or continued material breach of its obligations under these Terms and/or Order or shall have been guilty of conduct tending to bring itself into disrepute, on written notice to the Supplier/Service Provider when such work on the Order shall stop.
- 8.2 Transnet shall pay the Supplier/Service Provider a fair and reasonable price for justified work in progress, where such price reflects only those costs not otherwise recoverable by the Supplier/Service Provider, at the time of termination, and the Supplier/Service Provider shall give Transnet full assistance to check the extent of such work in progress. Payment of such price shall be in full and final satisfaction of any claims arising out of such termination and upon such payment the Supplier/Service Provider shall deliver to Transnet all work, including any materials, completed or in progress. The sum payable to the Supplier/Service Provider under this clause will not in any event exceed the total amount that would have been payable to the Supplier/Service Provider had the Order not been terminated.
- In the event of termination the Supplier/Service Provider must submit all claims within 2 [two] 8.3 months of termination after which time claims will only be met in what Transnet considers exceptional circumstances.
- 8.4 If the Goods or Services are not provided in accordance with an Order, the Order shall be deemed terminated and the Supplier/Service Provider shall compensate Transnet for any costs incurred in obtaining substitute Goods or any damage caused due to the failure or delay in the delivery.

#### 9 **ACCESS**

The Supplier/Service Provider shall be liable for the acts, omissions and defaults of its personnel or agents who, for the purposes of the Order, shall be treated as if they are the Supplier's/Service Provider's employees. The Supplier/Service Provider shall ensure that any such personnel or agents, whilst on Transnet's premises, shall comply with Transnet's health and safety, security and system security rules and procedures as and where required.

### 10 WARRANTY

The Supplier Service Provider warrants that it is competent to supply the Goods/Services in accordance with these Terms to the reasonable satisfaction of Transnet and that all Goods/Services delivered under the Order: (a) conform and comply in all relevant legislation, standards, directives and orders related to [inter alia] the Goods/Services in force at the time of delivery, and to any specifications referred to in the Order; (b) will not cause any deterioration in the functionality of any Transnet equipment; and (c) do not infringe any third party rights of any kind. The Supplier/Service Provider hereby indemnifies Transnet against all losses, liabilities, costs, claims, damages, expenses and awards of any kinds incurred or made against Transnet in connection with any breach of this warranty.

#### 11 INSOLVENCY

If the Supplier/Service Provider shall have a receiver, manager, administrator, liquidator or like person appointed over all or any part of its assets or if the Supplier/Service Provider compounds with its creditors

or passes a resolution for the writing up or administration of the Supplier/Service Provider, Transnet is at liberty to terminate the Order or Orders forthwith, or at its option, to seek performance by any such appointed person.

#### 12 ASSIGNMENT

The Supplier/Service Provider shall not assign its obligations under an Order without Transnet's prior written consent, which consent shall not be unreasonably withheld or delayed.

#### 13 NOTICES

Notices under these Terms shall be delivered by hand to the relevant addresses of the parties in the Order or may be served by facsimile or by email, in which event notice shall be deemed served on acknowledgement of receipt by the recipient.

#### **14 LAW**

Orders shall be governed by and interpreted in accordance with South African law and any disputes arising herein shall be subject to South African arbitration under the rules of the Arbitration Foundation of South Africa, which rules are deemed incorporated by reference in this clause. The reference to arbitration shall not prevent Transnet referring the matter to any South African courts, having jurisdiction, to which the Supplier/Service Provider hereby irrevocably submits but without prejudice to Transnet's right to take proceedings against the Supplier/Service Provider in other jurisdictions and/or obtaining interim relief on an urgent basis from a court of competent jurisdiction pending the decision in other courts or from instituting in any court of competent jurisdiction any proceedings for an interdict or any other injunctive relief. If the Supplier/Service Provider does not have a registered office in the South Africa it will at all times maintain an agent for service of process in South Africa and shall give Transnet the name and address of such agent as such may be amended, in writing, from time to time.

#### 15 GENERAL

Completion or termination of an Order shall be without prejudice to any Term herein which by its nature would be deemed to continue after completion or termination, including but not limited to clauses 5, 6, 7, and 10. Headings are included herein for convenience only. If any Term herein be held illegal or unenforceable, the validity or enforceability of the remaining Terms shall not be affected. No failure or delay by Transnet to enforce any rights under these Terms will operate as a waiver thereof by Transnet. All rights and remedies available to either party under these Terms shall be in addition to, not to the exclusion of, rights otherwise available at law.

## 16 COUNTERPARTS

These Terms and conditions may be signed in any number of counterparts, all of which taken together shall constitute one and the same instrument. Any party may enter into this agreement by signing any such counterpart.

By signing this RFQ document, the Respondent is deemed to acknowledge that he/she has made himself/herself thoroughly familiar with all the conditions governing this RFQ, including those contained in any printed form stated to form part hereof and Transnet SOC Ltd will recognise no claim for relief based on an allegation that the Respondent overlooked any such condition or failed to properly take it into account for the purpose of calculating quoted prices or otherwise.

SIGNED at		on this	day of	20
SIGNATURE OF RESPONDE		ISED REPRESE	NTATIVE	
NAME:	~			
DESIGNATION:				
REGISTERED NAME OF CO	MPANY:	~		
PHYSICAL ADDRESS:			•	11
			1	
Respondent's contact p	erson: [Please	e complete]	10.	
Name	:			
Designation	:			
Telephone	:	CITIES OF STATE OF ST		
Cell Phone	+ 0	1		
Facsimile				
Email	N			
Website	J.	71	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	327201100227001110
	•		`	

Transnet urges its clients, suppliers and the general public to report any fraud or corruption to TIP-OFFS ANONYMOUS: 0800 003 056

# Section 4 VENDOR APPLICATION FORM

oreview copy only

TRANSN



## Transnet Supplier Declaration/Application

The Financial Director or Company Secretary

Transnet Vendor Management has received a request to load your company on to the Transnet vendor database. Please furnish us with the following to enable us to process this request:

- 1. Complete the "Supplier Declaration Form" (SDF) on page 2 of this letter
- 2. Original cancelled cheque OR letter from the bank verifying banking details (with bank stamp)
- 3. Certified copy of Identity document of Shareholders/Directors/Members (where applicable)
- 4. Certified copy of certificate of incorporation, CM29 / CM9 (name change)
- 5. Certified copy of share Certificates of Shareholders, CK1 / CK2 (if CC)
- 6. A letter with the company's letterhead confirming physical and postal addresses
- 7. Original or certified copy of SARS Tax Clearance certificate and Vat registration certificate
- 8. A signed letter from the Auditor / Accountant confirming most recent annual turnover and percentage black ownership in the company AND/OR BBBEE certificate and detailed scorecard from an accredited rating agency (SANAS member).
- NB: Failure to submit the above documentation will delay the vendor creation process.
  - Where applicable, the respective Transnet business unit processing your application may request further information from you. E.g. proof of an existence of a Service/Business contract between your business and the respective Transnet business unit etc.

#### **IMPORTANT NOTES:**

- a) If your annual turnover is less than R5 million, then in terms of the DTI codes, you are classified as an Exempted Micro Enterprise (EME). If your company is classified as an EME, please include in your submission, a signed letter from your Auditor / Accountant confirming your company's most recent annual turnover is less than R5 million and percentage of black ownership and black female ownership in the company AND/OR BBBEE certificate and detailed scorecard from an accredited rating agency (e.g. permanent SANAS Member), should you feel you will be able to attain a better BBBEE score.
- b) If your annual turnover is between R5 million and R35million, then in terms of the DTI codes, you are classified as a Qualifying Small Enterprise (QSE) and you claim a specific BBBEE level based on any 4 of the 7 elements of the BBBEE score card, please include your BEE certificate in your submission as confirmation of your status.

  NB: BBBEE certificate and detailed scorecard should be obtained from an accredited rating agency (e.g. permanent SANAS Member).
- c) If your annual turnover is in excess of R35million, then in terms of the DTI codes, you are classified as a Large Enterprise and you claim a specific BEE level based on all seven elements of the BBBEE generic score-card. Please include your BEE certificate in your submission as confirmation of your status.
  NB: BBBEE certificate and detailed scorecard should be obtained from an accredited rating agency (permanent SANAS Member).
- d) To avoid PAYE tax being automatically deducted from any invoices received from you, you must also contact the Transnet person who lodged this request on your behalf, so as to be correctly classified in terms of Tax legislation.
- e) Unfortunately, <u>No payments can be made to a vendor until</u> the vendor has been registered, and no vendor can be registered until the vendor application form, together with its supporting documentation, has been received and processed.
- f) Please return the completed Supplier Declaration Form (SDF) together with the required supporting documents mentioned above to the Transnet Official who is intending to procure your company's services/products in order that he/she should complete and Internal Transnet Departmental Questionnaire before referring the matter to the appropriate Transnet Vendor Master Office.

Regards,

Transnet Vendor/Supplier Management .Contact person Carol tell: 021 940-3846 fax 021 940-3883.

TRANSN



## **Supplier Declaration Form**

Company Trading Name										
Company Registered Nam	<del>е</del>									
Company Registration Nun		er If A Sole Proj	orietor							
Form of entity	СС	Trust	Pty Ltd	L.	imited.	Part	nership		Sole Proprietor	
VAT number (if registered)						,				
Company Telephone Numb	per									
Company Fax Number										
Company E-Mail Address										
Company Website Address	5				~	Mariana Tanana				2011
Bank Name	Bank Account Number									
Postal Address		Code								
Physical Address		Literia						Code		
Contact Person						(	1			
Designation							7			
Telephone			-1-0-1/4							
Email								00000000000000000000000000000000000000		
Annual Turnover Range (L	ast Financial Yea	r)	< R5 Million		F	R5-35 million		>	>R35 million	
Does Your Company Provi	de		Products		Services			Both		
Area Of Delivery		National		Provincial		٤	-ocal			
Is Your Company A Public				Public		Į.	Private			
Does Your Company Have A Tax Directive Or IRP3			cate		Yes		1	Мo		
Main Product Or Service Supplied (E.G.: Stationery/			ing)			·····				
BEE Ownership Details							N			
%Black Ownership	9	% Black women ownership			% Disabled person/s ownership					
Does your company have a	BEE certificate			Yes			No	>		
What is your broad based f	BEE status (Level	to 9 / Unknow	wn)							
How many personnel does	the firm employ		Per	manen	t		Part time	₽		
Transnet Contact Person										
Contact number										
Transnet operating division										
Duly Authorised To Sign	For And On Beh	alf Of Firm / O	rganisation				φ			
Name	******************************				Des	ignation				
Signature					Date	<b>)</b>	.]			~,-,,
Stamp And Signature Of Commissioner Of Oath										
Name		>>>			Date	3				
Signature					Tele	phone No.		CCCC01111-1111-1011-		

NB: Please return the completed Supplier Declaration Form (SDF) together with the required supporting documents mentioned above to the Transnet Official who is intending to procure your company's services/products.

Transnet Vendor/Supplier Management .Contact person Carol tell: 021 940-3846 fax 021 940-3883

***************************************	
Respondent's Signature	Date & Company Stams

## Section 5

## **BREACH OF LAW FORM**

NAME OF ENTITY:
I/We
do hereby certify that <i>I/we have/have not been</i> found guilty during the preceding 5 [five] years of a serious breach of law, including but not limited to a breach of the Competition Act, 89 of 1998, by a court of law, tribunal or other administrative body. The type of breach that the Respondent is required to disclose excludes relatively minor offences or misdemeanours, e.g. traffic offences.
Where found guilty of such a serious breach, please disclose:
NATURE OF BREACH:
DATE OF BREACH:
Furthermore, I/we acknowledge that Transnet SOC Ltd reserves the right to exclude any Respondent
from the bidding process, should that person or entity have been found guilty of a serious breach of law,
tribunal or regulatory obligation.
SIGNED at on this day of20
SIGNATURE OF WITNESS SIGNATURE OF RESPONDENT

#### Section 6

#### SUPPLIER CODE OF CONDUCT

Transnet aims to achieve the best value for money when buying or selling goods and obtaining services. This however must be done in an open and fair manner that supports and drives a competitive economy. Underpinning our process are several acts and policies that any supplier dealing with Transnet must understand and support. These are:

- The Transnet Supply Chain Policy
- Section 217 of the Constitution the five pillars of Public PSCM [Procurement and Supply Chain Management]: fairness, equity, transparency, competitiveness and cost effectiveness;
- The Public Finance Management Act (PFMA);
- The Broad-Based Black Economic Empowerment Act [B-BBEE]; and
- The Prevention and Combating of Corrupt Activities Act.

This Code of Conduct has been included in this rfq to formally apprise prospective Transnet Suppliers of Transnet's expectations regarding the behaviour and conduct of its Suppliers.

## Prohibition of bribes, kickbacks, unlawful payments, and other corrupt practices

Transnet is in the process of transforming itself into a self-sustaining State Owned Company [SOC], actively competing in the logistics industry. Our aim is to become a world class, profitable, logistics organisation. As such, our transformation is focused on adopting a performance culture and to adopt behaviours that will enable this transformation.

- a) Transnet will not participate in corrupt practices and therefore expects its Suppliers to act in a similar manner.
  - transnet and its employees will follow the laws of this country and keep accurate business records that reflect actual transactions and payments to our Suppliers.


Employees must not accept or request money or anything of value, directly or indirectly, to:

- illegally influence their judgement or conduct or to ensure the desired outcome of a sourcing activity;
- win or retain business or to influence any act or decision of any decision stakeholders involved in sourcing decisions; or
- gain an improper advantage.
- There may be an occasion when a Supplier is confronted with fraudulent or corrupt behaviour by a Transnet employee. We expect our Suppliers to use our "Tip-offs Anonymous" Hot line to report these acts [0800 003 056].

- b) Transnet is firmly committed to the ideas of free and competitive enterprise.
  - Suppliers are expected to comply with all applicable laws and regulations regarding fair competition and antitrust.
  - Transnet does not engage with non-value adding agents or representatives solely for the purpose of increasing B-BBEE spend [fronting].
- c) Transnet's relationship with Suppliers requires us to clearly define requirements, exchange information and share mutual benefits.
  - Generally, Suppliers have their own business standards and regulations. Although
    Transnet cannot control the actions of our Suppliers, we will not tolerate any illegal
    activities. These include, but are not limited to:
    - misrepresentation of their product [e.g. origin of manufacture, specifications, intellectual property rights];
    - collusion;
    - failure to disclose accurate information required during the sourcing activity [e.g. ownership, financial situation, B-B8EE status];
    - corrupt activities listed above; and
    - harassment, intimidation or other aggressive actions towards Transnet employees.
  - Suppliers must be evaluated and approved before any materials, components, products
    or services are purchased from them. Rigorous due diligence is conducted and the
    Supplier is expected to participate in an honest and straight forward manner.
  - Suppliers must record and report facts accurately, honestly and objectively. Financial records must be accurate in all material respects.

## Conflicts of interest

A conflict of interest arises when personal interests or activities influence [or appear to influence] the ability to act in the best interests of Transnet. Examples include, but are not limited to:



Transnet employees having a financial interest in a bidding entity

Bidding entities are required to disclose any interest/s which exist between themselves and any employee and/or Transnet Board member.

#### CONTRACTUAL OBLIGATIONS

- The Contractor shall not make use of any sub-Contractor to perform the works or parts 1.1 thereof without prior permission from the Project Manager.
- The Contractor shall ensure that a safety representative is at site at all times. 1.2
- The Contractor shall comply with all applicable legislation and Transnet safety requirements 1.3 adopted from time to time and instructed by the Project Manager / Supervisor. Such compliance shall be entirely at his own cost, and shall be deemed to have been allowed for in the rates and prices in the contract.
- The Contractor shall, in particular, comply with the following Acts and Transnet 1.4 Specifications:-
- The Compensation for Occupational Injuries and Diseases Act, No. 130 of 1993. The 1.4.1 Contractor shall produce proof of his registration and good standing with the Compensation Commissioner in terms of the Act.
- The Occupational Health and Safety Act (Act 85 of 1993). 1.4.2
- The explosive Act No. 26 of 1956 (as amended). The Contractor shall, when applicable, 1.4.3 furnish the Project Manager / Supervisor with copies of the permits authorising him or his employees, to establish an explosives magazine on or near the site and to undertake blasting operations in compliance with the Act.
- The Contractor shall comply with the current Transnet Specification E.4E, Safety 1.4.4 Arrangements and Procedural Compliance with the Occupational Health and Safety Act, Act 85 of 1993 and Regulations and shall before commencement with the execution of the contract, which shall include site establishment and delivery of plant, equipment or materials, submit to the Project Manager / Supervisor.
- The Contractor shall comply with the current Specification for Works On, Over, Under or 1.4.5 Adjacent to Railway Lines and near High Voltage Equipment - E7/1, if applicable, and shall take particular care of the safety of his employees on or in close proximity to a railway line during track occupations as well as under normal operational conditions.
- The Contractor's Health and Safety Programme shall be subject to agreement by the Project 1.5 Manager / Supervisor, who may, in consultation with the Contractor, order supplementary and/or additional safety arrangements and/or different safe working methods to ensure full compliance by the Contractor with his obligations as an employer in terms of the Act.
- In addition to compliance with clause 1.4 hereof, the Contractor shall report all incidents in 1.6 writing to the Project Manager / Supervisor. Any incident resulting in the death of or injury to any person on the works shall be reported within 24 hours of its occurrence and any other incident shall be reported within 48 hours of its occurrence.
- The Contractor shall make necessary arrangements for sanitation, water and electricity at 1.7 these relevant sites during the installation of the equipments.
- A penalty charge of R1,000.00 per day will be levied for late completion. 1.8
- The Contractor shall supply a site diary (with triplicate pages). This book shall be used to 1.9 record any unusual events during the period of the work. Any delays to the work shall also be recorded such as delays caused by poor weather conditions, delays caused by permits being cancelled etc. The appointed Project Manager or Supervisor must countersign such delays. Other delays such as non-availability of equipment from 3rd party suppliers must be communicated to the Project Manager or Supervisor in writing.
- The Contractor shall supply a site instruction book (with triplicate pages). This book shall 1.10 be used to record any instructions to the Contractor regarding problems encountered on site - for example the quality of work or the placement of equipment. This book shall be filled in by the Project Manager or Supervisor and must be countersigned by the Contractor.

Date & Company Stamp

- 1.11 Both books mentioned in 1.9 and 1.10 shall be the property of Transnet Freight Rail and shall be handed over to the Project Manager or Supervisor on the day of energising or handing over.
- 1.12 All processes or the manufacture and assembly of the product components must be subjected to a quality assurance system.
- 1.13 The Contractor will assume full responsibility for assuring that the products purchased meet the requirements of Transnet Freight Rail for function, performance, and reliability, including purchased products from 3<sup>rd</sup> part suppliers/Manufacturers.
- The Contractor shall prove to Transnet Freight Rail that his equipment or those supplied from 3<sup>rd</sup> party suppliers/manufacturers confirms to Transnet freight rail specifications.
- 1.15 The Contractor will remain liable for contractual delivery dates irrespective of deficiencies discovered during workshop inspections.



#### Works Information

#### 2.0 Description of work

#### 2.1 BUSBARS, NEGATIVE BAR AND FLEXIBLE CONNECTORS

- 2.1.1 Transnet Freight Rail reserves the right to award the contract to Contractor with the quickest delivery period due to the urgency of this substation.
- 2.1.2 Supply and install all Aluminium busbars (50x25mm²) from Main Transformer to wall bushings complete with flexible connectors, to rectifier (50x25mm²), to reactor coil (127x12.5mm²), to positive isolator (127x12.5mm²), to negative bar (127x12.5mm²).
- 2.1.3 Relocate the negative bar in the outdoor yard to the rectifier bay with its associated cables as per site meeting. All visible cables shall be covered with metal box.
- 2.1.4 Supply shunt 4000A/50mV.
- 2.1.5 Supply security for the duration of the contract.
- 2.1.6 All busbar connections shall be silver tinned and connection grease shall be used.
- 2.1.7 Nuts and bolts on busbar connections shall be stainless steel.

### 2.2 SUPPLY AND INSTALLATION OF CABLES

- 2.2.1 Contractor shall supply and install all the control and power cables in accordance with the specifications BBC 0198 version 1 and CEE 0023 of 1990.
- 2.2.2 The Contractor shall re-use all the control cables to connect AC disconnects to the new panels.
- 2.2.3 The Contractor shall divide the existing trench in order to accommodate both the HT and LT cables by making use of brick laying.
- 2.2.4 The Contractor shall make provision for terminating the armoured cables both in the substation indoor building and outdoor yard.
- 2.2.5 The contractor shall supply all track breaker control cables and connect track breakers to the panel.
- 2.2.6 Contractor shall supply and connect cables for step-up transformer and reconnect it to the panel.
- 2.2.7 The Contractor shall supply joint kits and all necessary terminations.
- 2.2.8 Supply and install the auxiliary isolating switch control cable (50mm² x 4 core). The Contractor shall terminate and connect on the auxiliary transformer and inside the control panel.
- 2.2.9 The Contractor shall supply and connect the 95 mm 2 PVC insulated welding cable to interconnect all new and existing equipment to the DC earth leakage relay system.

2.2.10 The Contractor shall remove all unwanted cables and busbars in the outdoor yard near the main transformer. Where positive isolator and auxiliary isolating switch has been removed, substation wall should be repainted with matching existing colour.

#### 2.3 MECHANICAL INTERLOCKING DEVICES AND CHECKER PLATES

- 2.3.1 Supply and install an interlocking mechanism complete (similar to existing) of the key exchange type, which include the AC disconnects, positive isolator, auxiliary transformer short out links to the HT bay gate in the correct sequence in accordance with the specification BBB 5452 version 3.
- 2.3.2 Supply and install checker plates. Checker plates must be painted black.

#### 2.4 DIRECT CURRENT EARTH RELAY CIRCUIT

- 2.4.1 Supply and install the DC earth leakage relay. The DC earth leakage relay shall be mounted outside the control panel at a position pointed out by Transnet Freight Rail. The relay shall be enclosed in a polycarbonate box.
- 2.4.2 The Contractor shall connect all existing checker plates as well as existing equipment (all indoor steelwork) to the DC earth leakage system. The Contractor shall also supply any missing checker plates.
- 2.4.3 The Contractor shall replace the DC earth leakage arrangement (system) as per drawing CEE TBD 0007 and enclosed in 25 mm<sup>2</sup> PVC conduits against the walls. The crimping lugs of the interconnection cables shall be correspondingly marked with the busbar as shown on drawing CEE TBD 0007.
- 2.4.4 Only hexagon crimps will be accepted on all crimping lugs.
- 2.4.5 Resistance between the DC earth leakage busbar and the substation earthmat shall not be less than 25 Ohm.

#### 2.5 POSITIVE ISOLATOR PANEL

- 2.5.1 Supply and install 3 kV DC positive isolator panels in accordance with the specification BBB 4724 ver 4. The positive isolator shall be fitted with a 3 kV DC under voltage relay as per specification BBB 3005 version 1.
- 2.5.2 The entry position of the busbars into the panel shall be confirmed with Transnet Freight Rail before manufacturing of the panel. Contractor shall provide the required warning signs as per specification BBB 4724 ver 4 on the positive isolator panel.
- 2.5.3 Supply and install a busbar from the reactor coil to the positive isolator. The busbar entering the positive isolator shall be 100 mm X 10 mm thickness.
- 2.5.4 The new Positive Isolator shall be installed next to the new panels on the left side of the new Rectifier.

#### 2.6 AC PCB CONTROL PANEL AND AC/DC DISTRIBUTION PANEL

- 2.6.1 Remove the existing AC primary circuit breaker (PCB) and AC/DC distribution panels from site and transport them to Bloemfontein Infrastructure depot.
- 2.6.2 Supply and install AC PCB control panel and AC/DC distribution panels in accordance with the specification BBB 2721 version 10.
- 2.6.3 Supply and install 2 x Protection relays for main transformer, auxiliary supply, AC earth leakage protection.

- 2.6.4 The panel must be able to accommodate signalling transformer (step-up transformer, 400/6600 V).
- 2.6.5 The Contractor shall wire the tripping and lock out circuits in accordance with the drawings CEE TBK 0027 and CEE TBK 0028. The circuits shall be incorporated into the AC PCB control panel.
- 2.6.6 The Contractor shall wire all the track breaker cells inside the panel.
- 2.6.7 The panels shall cater for a 3 contactor changeover system to accommodate the supply from the isolating transformer as well as auxiliary LT supplies.
- 2.6.8 The Contractor shall rewire controls for the extractor fan and incorporate into the distribution panel.
- 2.6.9 Ensure room fan circuit is still working.
- 2.6.10 Transnet Freight Rail representative shall inspect all the panels on the Contractor's premises prior to delivery to site.
- 2.6.11 All direct current wiring shall be done in grey coloured wire.
- 2.6.12 Colour Red, White and Blue shall be used for AC circuits only. All alternating current wiring shall be colour coded using the standard colours red, white, blue and black for neutral.
- 2.6.13 Interior shall be done in gloss white and exterior shall be done in Eau- de- nil high gloss to SANS 1091 colour code no G22.
- 2.6.14 Panels shall be colour coated in accordance with SANS 1274.
- 2.6.15 Insulated lugs, of the crimp on type, shall be used to terminate wiring onto equipment, strip connectors and protection relays.
- 2.6.16 Screw on terminal lugs shall be used on all the protection relays.
- 2.6.17 All new and existing cables and wiring shall be clearly labelled by using an approved slide on wiring label system as described.
- 2.6.18 Where applicable, the Contractor will be responsible to connect and interconnect the control wiring and cabling of existing equipment to the new and old equipment.
- 2.6.19 The Contractor shall make provision for a connection strip in the AC/DC distribution panel and the primary circuit breaker control panel for remote tele-control operations.
- 2.6.20 The Contractor shall notify Transnet Freight Rail on completion of the panels in order to witness functional tests on the premises of the Contractor before delivery.
- 2.6.21 The Contractor shall incorporate all existing equipment functions into the schematic drawings as per specification CEE 0224 of 2002.
- 2.6.22 A copper busbar system consisting of a busbar for each phase red, white and blue shall be used, in the AC/DC panel and concealed behind perspex with warning sign and voltage identification label.
- 2.6.23 A copper busbar system consisting of battery supply, holding coil volts and negative shall be used and covered with perspex with a warning sign and voltage labels.

- 2.6.24 The Contractor shall supply and install the auxiliary supply switch inside the AC/DC control panel.
- 2.6.25 Provision will be made in the primary circuit breaker control panel to install primary overload protection for the auxiliary supply.
- 2.6.26 All control panels shall be insulated from the substation floor.
- 2.6.27 The layout of the AC and DC equipment inside the control panels shall be done in such a way that the equipment is separated from each other.
- 2.6.28 Transnet Freight Rail shall inspect the layout of the equipment before wiring commences of the panels.
- 2.6.29 All equipment used in the primary circuit breaker control panel and the AC/DC distribution panel shall comply with the SANS 0142.
- 2.6.30 Contractor shall supply his/her own security for the duration of the contract.

## 2.8 SUPPLY AND INSTALL OUTDOOR EARTH, RELOCATION OF SURGE ARRESTERS

- 2.8.1 Remove surge arresters from main transformer and install the surge arresters in accordance with Transnet's specifications BBB 0845 and BBB 0938 on a steel structure.
- 2.8.2 Connect surge arresters between each phase of the high voltage supply and the substation main earth in accordance with Transnet's specification BBB 3059 and drawing BBB 3620 version 3. The material used to connect the surge arresters and the earth spike shall be by means of copper clad steel rod.
- 2.8.3 Connect surge arresters to appropriate height between each phase of the high voltage supply and the substation main earth in accordance with Transnet's specification BBB 3059 and drawing BBB 3620 version 3. The material used to connect the surge arresters and the earth spike shall be by means of copper clad steel rod.
- 2.8.4 Design, supply and install support steel structures for the surge arresters. The manufacture of any steelwork shall not take place prior to the approval of the design drawings by Transnet. Transnet shall inspect the steelwork at the manufacturer's works prior to dispatch.
- 2.8.5 The top of the surge arresters and the bushings shall be on the same connection height.

#### 3 STEELWORK

- 3.1 The design, supply and installation of all steel structures for the support of equipment shall be the responsibility of the Contractor. This shall be in accordance with Transnet Freight Rail specification CEE.0183.2002.
- 3.1 The manufacture of any steelwork shall not take place prior to the approval of the design drawings by the Supervisor/ Electrical Officer.
- 3.2 Transnet Freight Rail shall inspect the steelwork at the manufacturers works prior to dispatch.
- 3.3 All fasteners (nuts & bolts) shall be secured using flat and spring washers where necessary.
- 3.4 All steelwork shall be galvanized in accordance with SANS 121 and, where required painted in accordance with specification CEE 045 of 2002/1.

#### 4 INSTALLATION

- 4.1 The Contractor shall be responsible for the transport to site, off-loading, handling, storage and security of all material required for the construction/execution of the works.
- 4.2 All fasteners on steelwork, components and electrical connections (nuts and bofts) shall be secured using flat as well as lock washers.
- 4.3 Contractor shall supply multi core cable and connect the tele-control. The substation shall not be switched on unless the tele-control is fully operational.

## 5 INTERCONNECTION OF EQUIPMENT

- 5.1 High conductive silicon grease shall be liberally applied to all the connections.
- 5.2 All dissimilar metal connections (Cu to AI) shall be made using bi-metallic clamps that are specifically designed and manufactured to make that particular connection (ad hoc fabricated clamps are not acceptable).

#### 6 SITE TESTS

- 6.1 The equipment shall be inspected /tested and approved by Transnet Freight Rail Quality Assurance at the Contractor's workshop prior to it being taken to site. Only once the approval has been granted can the equipment be taken to site for installation.
- 6.2 The Contractor shall be responsible for carrying out of on-site tests and commissioning of all equipment supplied and installed in terms of this specification and the contractual agreement.
- 6.3 Functional on-site tests shall be conducted on all items of equipment and circuitry to prove the proper functioning and installation thereof.
- 6.4 The Contractor shall submit a detailed list of on-site tests for the approval of the Project Manager or Supervisor.
- 6.5 The Contractor shall arrange for the Supervisor or his representative to be present to witness the on-site tests.
- 6.6 The on-site tests and subsequent commissioning <u>will not commence until ALL</u>

  <u>CONSTRUCTION</u> work has been completed. Construction staff, material and equipment shall be removed from site prior to the commencement of testing. Testing and commissioning of the power plants equipment will not be allowed to take place in a construction site environment.
- 6.7 The on-site tests shall include the following:
- 6.7.1 Test for the functionality of all electrical circuitry.
- 6.7.2 Trip tests on relays.
- 6.7.3 Test on equipment as per manufacturer's instructions.
- 6.7.4 Insulation tests.
- At the completion of the on-site tests, the Project Manager or Supervisor or his representative shall either sign the tests sheets (supplied by the Contractor) as having witnessed the satisfactory completion thereof, or hand to the Contractor a list of defects requiring rectification.
- 6.9 Upon rectification of defects, the Contractor shall arrange for the Project Manager or Supervisor or his representative to certify satisfactory completion of on-site tests.
- 6.10 Acceptance by the Project Manager or Supervisor of satisfactory completion of on-site tests in no way relieves the Contractor of his obligation to rectify defects which may have been overlooked or become evident at a later stage.

## 7 COMMISSIONING OF EQUIPMENT

7.1 Commissioning will only take place after all defects have been rectified to the satisfaction of the Project Manager or Supervisor.

- 7.2 On completion of commissioning, the Contractor will hand the equipment over to the Project Manager or Supervisor in terms of the relevant Instruction.
- 7.3 The commissioning of protection equipment by Transnet Freight Rail will in no way absolve the Contractor from any of his responsibilities during the guarantee period.
- 7.4 It is the Contractor's responsibility to satisfy himself or herself that the commissioning of the protection equipment has been carried out in a satisfactory manner, and in no way compromises the proper operation of the equipment supplied in terms of the contract.
- 7.5 The Contractor shall be present during the testing and setting of the protection to rectify any faults found.

#### 8 GUARANTEE AND DEFECTS

- 8.1 The Contractor shall guarantee the satisfactory operation of the complete electrical installation supplied and erected by him and accept liability for maker's defects that may appear in design, materials and workmanship for a period of 12 months.
- 8.2 The Contractor shall be issued with a completion certificate with the list of all defects to be repaired within 14 working days after commissioning.
- 8.3 Any defects that may become apparent during the guarantee period shall be rectified to the satisfaction of Transnet Freight Rail, and to the account of the Contractor.
- 8.4 The Contractor shall undertake work on the rectification of any defects that may arise during the guarantee period within 7-days of him being notified by Transnet Freight Rail of such defects.
- 8.5 Should the Contractor fail to comply with the requirements stipulated above, Transnet Freight Rail shall be entitled to undertake the necessary repair work or effect replacement of defective apparatus or materials, the total cost of such repair or replacements, including the labour costs incurred in replacing defective material shall be deducted from the Contractors payment.
- 8.6 Any specific type of fault occurring three times within the guarantee period and which cannot be proven to be due to other faulty equipment not forming part of this contract e.g., faulty locomotive or overhead track equipment, etc., shall automatically be deemed an inherent defect. Such inherent defect shall be fully rectified to the satisfaction of the Project Manager or Supervisor and at the cost of the Contractor.
- 8.7 If urgent repairs have to be carried out by Transnet Freight Rail staff to maintain supply during the guarantee period, the Contractor shall inspect such repairs to ensure that the guarantee period is not affected and should they be covered by the guarantee, reimburse Transnet Freight Rail the cost of material and labour.
- 8.8 The guarantee and service period for these substations shall expire after a period of 12 months commencing on the date of completion of the contract or the date the substation is handed over to Transnet Freight Rail whichever is the latest.
- 8.9 The specified guarantee period shall only apply to the new equipment installed and from the time of energising the equipment and the acceptance thereof.
- 8.10 Should the Contractor fail to comply with the requirements stipulated above, Transnet Freight Rail shall be entitled to undertake the necessary repair work or effect replacement of defective apparatus or materials, and Transnet freight rail shall reimburse from the retention money the total cost of such repair or replacements, including the labour costs incurred in replacing defective material

## 9 QUALITY AND INSPECTION

9.1. Transnet Freight Rail shall inspect the equipment under contract on the premises of the Manufacturer or successful Contractor.

- The Contractor shall notify Transnet Freight Rail 14 days in advance of such an inspection date.
- 9.3. The Contractor shall apply 14 days in advance for the date of energizing and ensure that all work is completed before any commissioning can take place.
- 9.4. The Contractor shall be responsible to issue a compliance certificate in terms of SANS 0142 for each site before energizing of the equipment shall take place.

## 10. Safety information

The Contractor shall comply with requirements of safety legislation and regulations in all respects.

Security of all of the Contractor's staff, vehicles, machinery, equipment and materials shall remain the responsibility of the Contractor. The Contractor may use Transnet Freight Rail premises from time to time but the responsibility and cost to provide security, which may be required, shall be for the Contractor's account. No separate payment shall be made and the cost thereof shall be deemed to be included in the rates tendered. Transnet Freight Rail shall entertain no claims whatsoever in this regard.

The Contractor shall prepare and submit to Transnet Freight Rail at the start of the contract, a comprehensive safety plan which shall also cover the following headings:

Transportation of flammable / explosive materials and / or equipment on the same road or rail vehicle as personnel.

Storing flammable/explosive materials and/or equipment.

Fire prevention and fire fighting plan.

Safety procedures for staff when working on double line sections.

Safe working procedure for all aspects of the operation, inclusive of all moving of machinery by rail if required by the Contractor.

The method of work shall be such that at all times it shall comply with Transnet Freight Rail Specification E7/1.

Normal protection measures in accordance with the Transnet Freight Rail Protection Manual shall apply.

All protection arrangements shall at all times remain under the supervision and responsibility of a Transnet Freight Rail Traction Linesman. No work is permitted if an occupation is not approved.

The Contractor shall not allow any persons on the work site to venture within the structure gauge of any adjacent line when this warning procedure is not operating effectively.

An effective safety procedure to be followed by all personnel on any work site in the case of approaching rail traffic shall be compiled by the Contractor and implemented before any work commences. This procedure shall be updated whenever the need arises and any changes shall be communicated to all employees on a work site before work proceeds.

All reasonable steps to effectively prevent the occurrence of veldt fires shall be required from the Contractor. Such fire fighting equipment and resources deemed necessary to effectively fight any veldt fire, which may occur as a result of the work, shall be required at each relay site and shall form part of this contract. The cost to provide such fire fighting equipment and resources shall be deemed to be included in the rates tendered and no separate payment shall be made for this.

No separate payment shall be made for the safety measures and the costs hereof will be deemed to be included in the rates tendered.

#### Training

#### General

The Contractor shall ensure that all staff working on or with the contract is adequately trained, so as to comply with any relevant safety and quality requirements.

It is the Contractor's responsibility to ensure that his personnel are trained. At the commencement of the contract, Transnet Freight Rail shall assist the contractor with the initial on-the-job training of the staff as specified below, so as to assist the Contractor to qualify the workers / staff. The Contractor shall ensure that he has a core group of workers with sufficient previous experience to take the lead in undertaking maintenance tasks.

Where the Contractor requires training and Transnet Freight Rail is committed to provide this training, the contractor shall quantify in his tender as to what and how many staff, training will be required. After award of the contract, the contractor shall then arrange with the appropriate Transnet Freight Rail Production Manager (OHTE), through the Technical Officer, for this training / testing.

The Contractor's Supervisor shall take full charge of the Contractor's resources on the work site. An employee / agent appointed by the contractor, will not act as, or be allowed to take on any responsibility as, the *person-in-charge-of-the-occupation*. The function of *person-in-charge-of-the-occupation* is restricted to competent Transnet Freight Rail employees only.

The *person-in-charge-of-the-occupation* shall be a competent Transnet Freight Rail employee, reporting to the Transnet Freight Rail Depot Engineering Manager. This person shall be responsible for the following on a work site:

Taking occupations
Cancelling the occupation
Communication with Control with regard to occupation matters.

The Transnet Freight Rail Depot Engineering Manager remains ultimately responsible in terms of the requirements of Act 85 for the safe working environment of his own personnel as well as contractor's personnel within the track maintenance environment on his depot.

The Depot Engineering Manager is therefore also responsible for ensuring that any changes in the Protection Procedures that may occur over time are effectively communicated his own personnel as well as contractor's personnel within the track maintenance environment on his depot

Electrical awareness, Educational and competency training

The following training shall be arranged for the following Contractors staff:

The electrical awareness training must be arranged for beforehand on-the-job. a)

The electrical educational and competency training may be arranged for at either a depot's lecture room (Transnet Freight Rail property), or at a venue of the Contractors choice (Contractors cost).

Transnet Freight Rail will provide the Accredited Electrical Trainer, from Transnet Freight Rail, at Transnet Freight Rail cost, provided that an arrangement for the training session required, is done beforehand and will fit in with the Trainers training program for the year.

Course	Objective	Duration & trainer	Grade to attend
A)Awareness (Electrical)	To inform all contractors staff working near a machine and on the line on electrified sections of the dangerous situations of high voltage OHTE and substations.	Two-hour on-the-job lecture and training.  Accredited Electrical  Trainer / Depot's Electrical technical officer.	All workers and staff working on the contract
B)PWC <b>Educational</b> (Electrical)	For the safe working on and with On-track machinery in the vicinity or near exposed High voltage OHTE and substations.	Lecture room training = 1,25 d On-the-job training =0,25 d Criterion test = 0,5 d Total = 2 days Accredited Electrical trainer	Workers working on a machine (High risk area's)     Operators     Machine fitters     Area supervisors     Contract supervisors
C) COM Competency (Electrical) (To follow A) (PWC)	Work permits safe working procedures under the direct supervision of a responsible representative.	Lecture room training = 0,25 d On-the-job training = 0,25 d Criterion test = 0,5 days Total = 1 day Accredited Electrical trainer	Supervisor (Responsible person in charge at machine working)

## 11. Specifications

## 11.1. South African National Standards:

SANS 121 SANS 8528	National colour standard. Hot dip galvanised zinc coating. Hot Dip Galvanised Coating for Fabricated Iron or Steel Article. Reciprocating internal combustion engine driven alternating current generating set. Wiring Code.
Transnet Freight Rail:	
BBB 0496 version 12	3 kV rectifier for traction substations.
BBB 3620 version 4	3kV DC earthing arrangement – Traction Substation.
BBB 5452 version 3	Transnet freight rail requirements for installation of electrical equipment for 3 kV DC substations.
BBB 2721 version 10	AC Primary Circuit Breaker Control Panel and AC/DC Distribution Panel for 3kV DC Traction substation.
CEE-TBD-0007	Earthing arrangement for traction substations.
CEE TBK 0027	Control circuit diagrams – NO volt operation.
	SANS 763 SANS 121 SANS 8528 SANS 10142

11.2.7 CEE TBK 0028	Trip, lockout and indication circuit diagram.
11.2.8 BBB 4724 version 4	Positive Isolator switch for 3 kV DC Traction substations.
11.2.9 BBB 3005 version 1	3 kV DC under voltage relay manufacturing specification.
11.2.10 BBC 0198 version 1	Specifications for the supply of cables.
11.2.11 CEE.0023.90	Specifications for installation of cables.
11.2.12 CEE.0045.2002/1	Painting of steel Components of Electrical Equipment.
11.2.13 CEE.0183.2002	Hot dip galvanising and painting of electrical equipment.
11.2.14 CEE.0224.2002	Drawings, catalogues, instruction manuals and spares list for
	electrical equipment supplied under contract

## NOTE: Any other specifications referenced in the above mentioned specification, will be for information purposes and may be provided on request.

11.3 Occupational Health and Safety Act No. 85 of 1993 (Available at depot for referral)

#### 12. Constraints on how the Contractor Provides the Works


12.1 The constraints shall be as specified in the specifications of the particular equipment.

## 13. Requirements for the programme

13.1	Programme of work	: To be submitted by successful Contractor
13.2	CIDB rating	: 2EPPE OR 3EP and above
13.3	Format	: Bar chart
13.3	Information	: How work is going to be executed and commissioned
13.4	Submission	: Not Applicable
13.5	Site diary	: Successful Contractor to supply in triplicates carbon copies
13.6	Site instruction book	: Successful Contractor to supply in triplicates carbon copies

## 14. Services and other things provided by the Employer

- 14.1 Transnet Freight Rail shall have an electrician available for isolation and the erection of barriers to live electrical equipment and issuing of work permits.
- 14.2 Upon successful completion of the works to the satisfaction of Transnet Freight Rail, Transnet Freight Rail shall perform necessary protection tests and commission the equipment.



#### TRANSNET SOC LIMITED

(Registration no. 1990/000900//30)

## SAFETY ARRANGEMENTS AND PROCEDURAL COMPLIANCE WITH THE OCCUPATIONAL HEALTH AND SAFETY ACT (ACT 85 OF 1993) AND APPLICABLE REGULATIONS

#### 1. General

- 1.1 The Contractor and Transnet Limited (hereinafter referred to as "Transnet") are individual employers, each in its own right, with their respective duties and obligations set out in the Occupational Health and Safety Act, Act 85 of 1993 (the Act) and applicable Regulations.
- 1.2 The Contractor accepts, in terms of the General Conditions of Contract and in terms of the Act, his obligations as an employer in respect of all persons in his employ, other persons on the premises or the Site or place of work or on the work to be executed by him, and under his control. He shall, before commencement with the execution of the contract work, comply with the provisions set out in the Act, and shall implement and maintain a Health and Safety Plan as described in the Construction Regulations, 2003 and as approved by Transnet, on the Site and place of work for the duration of the Contract.
- The Contractor accepts his obligation to complying fully with the Ast and applicable Regulations notwithstanding the omission of some of the provisions of the Act and the Regulations from this document.
- 1.4 Transnet accepts, in terms of the Act, its obligations as an employer of its own employees working on or associated with the site or place of work, and the Contractor and Technical Officer or his deputy shall at all times, co-operate in respect of the health and safety management of the site, and shall agree on the practical arrangements and procedures to be implemented and maintained during execution of the Works.
- 1.5 In the event of any discrepancies between any legislation and this specification, the applicable legislation will take precedence.

### 2. Definitions

- 2.1 In this Specification any word or expression to which a meaning has been assigned in the Construction Regulations, shall have the meaning so assigned to it, unless the context otherwise indicates: -
- The work included in this Contract shall for the purposes of compliance with the Act be deemed to be "Construction Work", which, in terms of the Construction Regulations, 2003 means any work in connection with:
  - the erection, maintenance, alteration, renovation, repair, demolition or dismantling of or addition to a building or any similar structure;
  - the installation, erection, dismantling or maintenance of fixed plant where such work includes the risk of a person falling;
  - (c) the construction, maintenance, demolition or dismantling of any bridge, dam, canal, road, railway, runway, sewer or water reticulation system or any similar civil engineering structure; or
  - (d) the moving of earth, clearing of land, the making of an excavation, piling, or any similar type of work;
- 2.3 "competent person" in relation to construction work, means any person having the knowledge, training and experience specific to the work or task being performed: Provided that where appropriate qualifications and training are registered as per the South African Qualifications Authority Act, 1995 these qualifications and training shall be deemed to be the required qualifications and training;
- 2.4 "contractor" means principal contractor and "subcontractor" means contractor as defined by the Construction Regulations, 2003.
- 2.5 "fall protection plan" means a documented plan, of all risks relating to working from an elevated position, considering the nature of work undertaken, and setting out the procedures and methods applied to eliminate the risk;

- 2.6 "health and safety file" means a file, or other record in permanent form, containing the information required to be kept on site in accordance with the Act and applicable Regulations;
- 2.7 **"Health and Safety Plan"** means a documented plan which addresses the hazards identified and include safe work procedures to mitigate, reduce or control the hazards identified;
- 2.8 "Risk Assessment" means a programme to determine any risk associated with any hazard at a construction site, in order to identify the steps needed to be taken to remove, reduce or control such hazard;
- 2.9 "the Act" means the Occupational Health and Safety Act No. 85 of 1993.

#### 3. Procedural Compliance

- 3.1 The Contractor who intends to carry out any construction work shall, before carrying out such work, notify the Provincial Director in writing if the construction work:-
  - (a) includes the demolition of a structure exceeding a height of 3 metres; or
  - (b) includes the use of explosives to perform construction work;
  - (c) includes the dismantling of fixed plant at a height greater than am,

and shall also notify the Provincial Director in writing when the construction work exceeds 30 days or will involve more than 300 person days of construction work and if the construction work:

- (a) includes excavation work deeper than Impor
- (b) includes working at a height greater than 3 metres above ground or a landing.
- The notification to the Provincial Director shall be on a form similar to Annexure A of the Construction Regulations, 2003, also shown in Annexure 1 of this Specification. The Contractor shall ensure that a copy of the completed notification form is kept on site for inspection by an inspector, Technical Officer or employee.
- 3.3 The Contractor shall, in accordance with the Act and applicable Regulations, make all the necessary appointments of competent persons in writing on a form similar to Annexure 2 of this Specification and deliver copies thereof to the Technical Officer. Copies should also be retained on the health and safety file.
- 3.4 Subcontractors shall also make the above written appointments and the Contractor shall deliver copies thereof to the Technical Officer.
- In the case of a self-employed Contractor or any subcontractor who has the appropriate competencies and supervises the work himself, the appointment of a construction supervisor in terms of regulation 6.1 of the Construction Regulations, 2003 will not be necessary. The Contractor shall in such a case execute and sign a declaration, as in Annexure 3, by which he personally undertakes the duties and obligations of the "Chief Executive Officer" in terms of section 16(1) of the Act.
- 3.6 The Contractor shall, before commencing any work, obtain from the Technical Officer an access certificate as in Annexure 4 executed and signed by him, permitting and limiting access to the designated site or place of work by the Contractor and any subcontractors under his control.
- 3.7 Procedural compliance with Act and Regulations, as above, shall also apply to any subcontractors as employers in their own right. The Contractor shall furnish the Technical Officer with full particulars of such subcontractors and shall ensure that they comply with the Act and Regulations and Transnet's safety requirements and procedures.

#### 4. Special Permits

Where special permits are required before work may be carried out such as for hotwork, isolation permits, work permits and occupations, the Contractor shall apply to the Technical Officer or the relevant authority for such permits to be issued. The Contractor shall strictly comply with the conditions and requirements pertaining to the issue of such permits.

## 5. Health and Safety Programme

- The Tenderer shall, with his tender, submit a Health and Safety Programme setting out the practical arrangements and procedures to be implemented by him to ensure compliance by him with the Act and Regulations and particularly in respect of: -
  - (i) The provision, as far as is reasonably practical, of a working environment that is safe and without risk to the health of his employees and subcontractors in terms of section 8 of the Act;
  - (ii) the execution of the contract work in such a manner as to ensure in terms of section 9 of the Act that persons other than those in the Contractor's employment, who may be directly affected by the contract work are not thereby exposed to hazards to their health and safety;
  - (iii) ensuring, as far as is reasonably practical, in terms of section 37 of the Act that no employee or subcontractor of the Contractor does or omits to do any act which would be an offence for the Contractor to do or omit to do.
- The Contractor's Health and Safety Programme shall be based on a risk assessment in respect of the hazards to health and safety of his employees and other persons under his control that are associated with or directly affected by the Contractor's activities in performing the contract work and shall establish precautionary measures as are reasonable and practical in protecting the safety and health of such employees and persons.
- 5.3 The Contractor shall cause a risk assessment contemplated in clarge 5.2 above to be performed by a competent person, appointed in writing, before commencement of any Construction Work and reviewed during construction. The Risk Assessments shall form part of the Pealth and Safety programme to be applied on the site and shall include at least the following:
  - (a) The identification of the risks and hazards that persons may be exposed to;
  - (b) the analysis and evaluation of the hazards identified;
  - a documented Health and Safety Plan, including safe work procedures to mitigate, reduce or control the risks identified;
  - (d) a monitoring and review plan.
- 5.4 The Health and Safety Plan shalf include full particulars in respect of: -
  - (a) The safety management structure to be instituted on site or place of work and the names of the Contractor's health and safety representatives and members of safety committees where applicable.
    - (b) the sale working methods and procedures to be implemented to ensure the work is performed in compliance with the Act and Regulations;
  - the safety equipment, devices and clothing to be made available by the Contractor to his employees;
  - (d) the site access control measures pertaining to health and safety to be implemented;
  - (e) the arrangements in respect of communication of health and safety related matters and incidents between the Contractor, his employees, subconfractors and the Technical Officer with particular reference to the reporting of incidents in compliance with Section 24 and General Administrative Regulation 8 of the Act and with the pertinent clause of the General Conditions of Contract forming part of the Contract and
  - (f) the introduction of control measures for ensuring that the Safety Plan is maintained and monitored for the duration of the Contract.
- 5.4 The Health and Safety programme shall be subject to the Technical Officer's approval and he may, in consultation with the Contractor, order that additional and/or supplementary practical arrangements and procedures be implemented and maintained by the Contractor or that different working methods or safety equipment be used or safety clothes be issued which, in the Technical Officer's opinion, are necessary to ensure full compliance by the Contractor with his obligations as an employer in terms of the Act and Regulations. The Technical Officer or his deputy shall be allowed to attend meetings of the Contractor's safety committee as an observer.

- 5.5 The Contractor shall take reasonable steps to ensure that each subcontractor's Health and Safety Plan is implemented and maintained on the construction site: Provided that the steps taken, shall include periodic audits at intervals mutually agreed to between the them, but at least once every month.
- 5.6 The Contractor shall stop any subcontractor from executing any construction work, which is not in accordance with the Contractor's, and/or subcontractor's Health and Safety Plan for the site or which poses a threat to the health and safety of persons.
- 5.7The Contractor shall ensure that a copy of the Health and Safety Plan is available on site for inspection by an inspector, Technical Officer, agent, subcontractor, employee, registered employee organisation, health and safety representative or any member of the health and safety committee.
- 5.8 The Contractor shall consult with the health and safety committee or, if no health and safety committee exists, with a representative group of employees, on the development, monitoring and review of the Risk Assessment.
- 5.9The Contractor shall ensure that all employees under his control are informed, instructed and trained by a competent person regarding any hazard and the related work procedures before any work commences, and thereafter at such times as may be determined in the Risk Assessment.
- 5.10 The Contractor shall ensure that all subcontractors are informed regarding eoy hazard as stipulated in the Risk Assessment before any work commences, and thereafter at such times as may be determined in the Risk Assessment.
- 5.11 The Contractor shall ensure that all visitors to a construction site undergoes health and safety induction pertaining to the hazards prevalent on the site and shall be provided with the necessary personal protective equipment.

#### 6. Fall Protection Plan

- 6.1.1 In the event of the risk and hazard identification, as required in terms of clause 5.3 of this Specification, revealing risks relating to working from an elevated position the contractor shall cause the designation of a competent person, responsible for the preparation of a fall protection plan;
- 6.2 The Contractor shall implement, maintain and monitor the fall protection plan for the duration of Contract.

  The Contractor shall also take such steps to ensure the continued adherence to the fall protection plan.
- 6.3 The fall protection plan shall include:-
  - (ā) A Risk Assessment of all work carried out from an elevated position;
  - (b) the procedures and methods to address all the identified risks per location;
  - (c) the evaluation of the employees physical and psychological fitness necessary to work at elevated positions;
  - (d) the training of employees working from elevated positions; and
  - (e) the procedure addressing the inspection, testing and maintenance of all fall protection equipment.

#### 7. Hazards and Potential Hazardous Situations

The Contractor and the Technical Officer shall immediately notify one another of any hazardous or potentially hazardous situations which may arise during performance of the Contract by the Contractor or any subcontractor and, in particular, of such hazards as may be caused by the design, execution and/or location and any other aspect pertaining to the contract work.

#### 8. Health and Safety File

8.1 The Contractor shall ensure that a health and safety file is opened and kept on site and shall include all documentation required as per the Act and applicable regulations, and made available to an inspector, the Technical Officer, or subcontractor upon request.

- 8.2 The Contractor shall ensure that a copy of the both his Health and Safety Plan as well as any subcontractor's Health and Safety Plan is available on request to an employee, inspector, contractor or the Technical Officer.
- 8.3 The Contractor shall hand over a consolidated health and safety file to the Technical Officer upon completion of the Construction Work and shall in addition to documentation mentioned in the Act and applicable Regulations include a record of all drawings, designs, materials used and other similar information concerning the completed structure.

preview copy

#### OCCUPATIONAL HEALTH AND SAFETY ACT, 1993

#### Regulation 3(1) of the Construction Regulations

#### NOTIFICATION OF CONSTRUCTION WORK

1(a)	Name and postal address of principal contractor:
(b)	Name and tel, no of principal contractor's contact person:
2.	Principal contractor's compensation registration number:
3.(a)	Name and postal address of client:
(b)	Name and tel no of client's contact person or agent:
۶.(a)	Name and postal address of designer(s) for the project:
(b)	Name and tel. no of designer(s) contact person:
5.	Name and telephone number of principal contractor's construction supervisor on site appointed in terms of regulation 6(1).
S.	Name/s of principal contractor's construction sub-ordinate supervisors on site appointed in terms of regulation 6(2).
7,	Exact physical address of the construction site or site office:
3.	Nature of the construction work:
),	Expected commencement date:
O	Expected completion date:

11. E	istimated maximum number of persons on the construction site:	
12. P	Planned number of contractors on the construction site accountable to	the principle contractor:
13.	Name(s) of contractors already chosen.	
Princ	ipal Contractor	Date
Client	†	Date

- \* THIS DOCUMENT IS TO BE FORWARDED TO THE OFFICE OF THE DEPARTMENT OF LABOUR <u>PRIOR</u>
  TO COMMENCEMENT OF WORK ON SITE.
- \* ALL PRINCIPAL CONTRACTORS THAT QUALIFY TO NOTIFY MUST DO SO EVEN IF ANOTHER PRINCIPAL CONTRACTOR ON THE SAME SITE HAD DONE SO PRIOR TO THE COMMENCEMENT OF WORK.

#### (COMPANY LETTER HEAD)

#### OCCUPATIONAL HEALTH AND SAFETY ACT, 1993 (ACT 85 OF 1993):

SECTION/REGULATION:	
REQUIRED COMPETENCY:	
In terms of	1,
representing the Employer) do hereby	e appoint
As the Competent Person on the prem	rises at
(physical address) to assist in complia	nce with the Act and the applicable Regulations.
Your designated area/s is/are as follow	7/5 :-
V-M-I	
Date:	
Signature :-	
Designation :-	
in the School of	ACCEPTANCE OF DESIGNATION
I,	do hereby accept this Designation and acknowledge that I
understand the requirements of t	his appointment.
Date:	
Signature :-	
Designation :-	

#### (COMPANY LETTER READ)

#### OCCUPATIONAL HEALTH AND SAFETY ACT, 1993 (ACT 85 OF 1993):

#### DECLARATION

In terms of the above Act. I, and obligations as Chief Executive. Officer, defined in Sect far as is reasonably practicable, ensure that the duties a above Act are properly discharged.	am personally assuming the duties ion I of the Act and in terms of Section 16(1), I will, as nd obligations of the Employer as contemplated in the
Signature :-  Date :	
review	

#### (LETTER HEAD OF BUSINESS DIVISION OR UNIT OF TRANSNET LIMITED)

#### SITE ACCESS CERTIFICATE

Access to :	(Area)
Name of Contractor/Builder : Contract/Order No.:	
contract, officer state,	
The contract works site/area described	l above are made available to you for the carrying out of associated works
In terms of your contract/order with (company)	
Kindly note that you are at all times under your control having access to the	responsible for the control and safety of the Works Site, and for persons e site.
<ul> <li>and Safety Act, 1993 (Act 85 of 1993).</li> </ul>	sponsible for compliance with the requirements of the Occupational Health as amended, and all conditions of the Contract pertaining to the site of the econtract documents including the plans of the site or work areas forming
Signed :	Date :
A	CKNOWLEDGEMENT OF RECEIPT
Name of Contractor/Builder	T,
	do hereby acknowledge and accept the duties
and obligations in respect of the Health and Safety Act; Act 85 of 1	Safety of the site/area of Work in terms of the Occupational 993.
Name :	Designation :
Signature :	Date:

TRANSMET



Transnet SOC Limited Registration Number 1596/00500/00

### TRANSNET SPECIFICATION

# E7/1 - SPECIFICATION FOR GENERAL WORK AND WORKS ON, OVER, UNDER OR ADJACENT TO RAILWAY LINES AND NEAR HIGH VOLTAGE EQUIPMENT

(This specification shall be used in network operator contracts)

Circulation Not Restricted

O This document as a whole is protected by copyright. The information herein is the sole property of Transnot SOC Ltd. It may not be used, disclosed or reproduced in part or in whole in any manner whatsoever, except with the written permission of and in a manner permitted by the proprietors.

(This page not to be issued with contract)

reviei

## SPECIFICATION FOR GENERAL WORK AND WORKS ON, OVER, UNDER OR ADJACENT TO RAILWAY LINES AND NEAR HIGH VOLTAGE EQUIPMENT

Author:	Project Wanager Capital Program (Electrical)	G, Maposa	Mulposa
Approved:	Senior Engineer Infra Engineering (Train Authorisation Systems)	J. van den Berg	
e e	Principal Engineer Infra Engineering (Track)	M. Marufia	H-C
A	Principal Engineer Infra Engineering (Structures)	J. Remari	
	Principal Engineer Infra Engineering (Electrical)	J. Vosico	Milwo
e.	Principal Engineer Technology Management (Electrical)	W. Coetzee	MAlaker
;t	Chier Engineer Transport Telecoms	D, Botha	On B. A.
Authorised:	Chief Engineer Infrastructure Engineering	J. van Aardt	Jalan 2011/06/30
		Date	e: May 2011

(This page not to be issued with contract)

TRANSNET



Transnet SOC Limited Registration Number 1990/00900/08

## TRANSNET SPECIFICATION

## E7/1 - SPECIFICATION FOR GENERAL WORK AND WORKS ON, OVER, UNDER OR ADJACENT TO RAILWAY LINES AND NEAR HIGH VOLTAGE EQUIPMENT

(This specification shall be used in network operator contracts)

Circulation Not Restricted

© This document as a whole is protected by copyright. The information herein is the sole properly of Transnet SOC Ltd. It may not be used, disclosed or reproduced in part or in whole in any manner whatsoever, except with the written permission of and in a manner permitted by the proprietors.

CONTENTS

CLAUSE	<u>HEADING</u>	PAGE
1.0	SCOPE	3
2.0	DEFINITIONS	3
	PART A - GENERAL SPECIFICATION	
3.0	AUTHORITY OF OFFICERS OF TRANSNET	4
4.0	CONTRACTOR'S REPRESENTATIVES AND STAFF	4
5.0	OCCUPATIONS AND WORK PERMITS	4
6.0	SPEED RESTRICTIONS AND PROTECTION	5
7.0	ROADS ON THE NETWORK OPERATOR'S PROPERTY	5
8.0	CLEARANCES	5
9.0	STACKING OF MATERIAL	5
10.0	EXCAVATION, SHORING, DEWATERING AND DRAMAGE	5
11.0	FALSEWORK FOR STRUCTURES	6
12.0	PILING	6
13.0	UNDERGROUND SERVICES	6
34.0	BLASTING AND USE OF EXPLOSIVES	6
15.0	RAIL TROLLEYS	7
16.6	SIGNAL TRACK CIRCUITS	7
17.0	PENALTY FOR DELAYS TO TRAINS	7
18.0	SURVEY BEACONS AND PEGS	7
19.0	TEMPORARY LEVEL CROSSINGS	8
20.0	COMPLETION OF THE WORKS	8
21.0	PROTECTION OF PERSONS AND PROPERTY	9
22.0	INTERFERENCE WITH THE NETWORK OPERATOR'S ASSETS AND WORK ON OPEN LINES	10
23.0	ACCESS, RIGHTS-OF-WAY AND CAMPSITES	10
24.0	SUPERVISION	10
25.0	HOUSING OF EMPLOYEES	10
26.0	OPTICAL FIDRE CABLE ROUTES	10
	ADDITIONAL SPECIFICATION FOR WORK NEAR HIGH-VOLTAGE ELECTRICAL EQU	IPMENT
27.0	GENERAL	11
28.0	WORK ON BUILDINGS OR FIXED STRUCTURES	11
20.0 29.0	WORK DONE ON OR OUTSIDE OF ROLLING STOCK, INCLUDING LOADING AND	
200	UNEOADING	11
30 0	USE OF EQUIPMENT	12
31 0	CARRYING AND HANDLING MATERIAL AND EQUIPMENT	12
32.0	PRECAUTIONS TO BE TAKEN WHEN ERECTING OR REMOVING POLES,	
	ANTENNAE AND TREES ETC	12
33 0	USE OF WATER	13
34 0	USE OF CONSTRUCTION PLANT	13
35-0	WORK PERFORMED UNDER DEAD CONDITIONS UNDER COVER OF A WORK PERMIT	13
36-0	TRACTION RETURN CIRCUITS IN RAILS	13
37.0	HIGH-VOLTAGE ELECTRICAL EQUIPMENT NOT MAINTAINED AND/OR OPERATED BY THE NETWORK OPERATOR	14

#### 1.0 SCOPE

1.1 This specification covers the network operator's requirements for general work and works on, over, under or adjacent to rariway lines and near high voltage equipment.

#### 2.0 DEFINITIONS

The following definitions shall apply

"Authorised Person" - A person whether an employee of the network operator or not, who has been specially authorised to undertake specific duties in terms of Transnet' publication Electrical Safety Instructions, and who holds a certificate or letter of authority to that effect.

"Barrier" Any device designed to restrict access to "live" high-voltage electrical equipment.

"Bond" - A short conductor installed to provide electrical continuity.

"Contractor" - Any person or organisation appointed by the network operator to carry out work on its behalf.

"Contract Supervisor" - The person or juristic person appointed by the network operator from time to time as the Contract Supervisor, to administer the Contractor's performance and execution of the Works according to the powers and rights held by and obligations placed upon the Contract Supervisor in terms of the Contract.

"Dead" - Isolated and earthed.

"Electrical Officer (Contracts)" - The person appointed in writing by the Project Manager in terms of this specification as the person who shall be consulted by the Contractor in all electrical matters to ensure that adequate safety precautions are taken by the Contractor.

"Executive Officer" - The person appointed by the network operator from time to time as the Executive Officer to act according to the rights and powers held by and obligations placed upon him in terms of the Contract.

"High-Voltage" - A voltage normally exceeding 1000 volts

"Live". A conductor is said to be "live" when it is at a potential different from that of the earth or any other conductor of the system of which it forms a part.

"Near" - To be in such a position that a person's body or the tools he is using or any equipment he is handling may come within 3 metres of live" exposed high-voltage electrical equipment.

"Occupation" - An authorisation granted by the network operator for work to be carried out under specified conditions on, over, under or adjacent to railway lines.

"Occupation Between Trains" - An occupation during an interval between successive trains.

\*Optical Fibre Cable\* Burled or suspended composite cable containing optical fibres used in:

- telecommunication networks for transmission of digital information and
- safety sensitive train operations systems.

"Project Manager" - As defined in the special conditions of the contract. The person or juristic person appointed by the network operator from time to time as the Project Manager, to administer the Contract according to the powers and rights held by and obligations placed upon him in terms of the Contract.

"Responsible Representative" - The responsible person in charge, appointed by a contractor, who has undergone specific training (and holds a certificate) to supervise (general or direct) staff under his control who perform general work or to work on, over, under or adjacent to railway lines and in the vicinity of high-voltage electrical equipment.

"Total Occupation" - An occupation for a period when trains are not to traverse the section of line covered by the occupation

"Work on" - Work undertaken on or so close to the equipment that the specified working degrances to the "five" equipment cannot be maintained

Work Permit" - A combined written application and authority to proceed with work on or near dead electrical equipment

"Works" - The contractual intent for the work to be done as defined in the contract at a defined work site

#### PART A - GENERAL SPECIFICATION

#### 3.0 AUTHORITY OF OFFICERS OF TRANSNET

- 3.1 The Contractor shall co-operate with the officers of the network operator and shall comply with all instructions issued and restrictions imposed with respect to the Works which bear on the existence and operation of the network operator's railway lines and high-voltage equipment.
- 5.2 Without limiting the generality of the provisions of clause 3.1, any duly authorised representative of the network operator, having identified himself, may stop the work if, in his opinion, the safe passage of trains of the safety of the network operator's assets or any person is affected CONSIDERATIONS OF SAFETY SHALL TAKE PRECEDENCE OVER ALL OTHER CONSIDERATIONS.

#### 4.0 CONTRACTOR'S REPRESENTATIVES AND STAFF

- The Contractor shall nominate Responsible Representatives of whom at least one shall be available at any hour for call-out in cases of emergency. The Contractor shall provide the Contract Supervisor with the names, addresses and telephone numbers of the representatives.
- 4.2 The Contractor guarantees that he has satisfied himself that the Responsible Representative is fully conversant with this specification and that he shall comply with all his obligations in respect thereof.
- 4.3 The Contractor shall ensure that all contractor staff receives relevant awareness, educational and competence training regarding safety as prescribed.
- 5.6 OCCUPATIONS AND WORK PERMITS
- 5.1 Work to be done during total occupation or during an occupation between trains or under a work permit shall be done in a manner decided by the Contract Supervisor and at times to suit the network operator requirements.
- 5.2 The Contractor shall organise the Works in a mariner which will minimise the number and duration of occupations and work permits required
- The network operator will not be liable for any financial or other loss suffered by the Contractor arising from his failure to complete any work scheduled during the period of an occupation or work permit.
- 5.4 The Contractor shall submit to the Contract Supervisor, in writing, requests for occupations or work permits together with details of the work to be undertaken, at least 21 days before they are required. The network operator does not undertake to grant an occupation or work permit for any particular date, time or duration.
- The network operator reserves the right to cancel any occupation or work permit at any time before or during the period of occupation or work permit. If, due to cancellation or change in date or time, the Contractor is not permitted to start work under conditions of total occupation or work permit at the time arranged, all tosts caused by the cancellation shall be born by the Contractor except as provided for in clauses 5 o to 5.8.
- 5.6 When the Contractor is notified tess than 2 hours before the scheduled starting time that the occupation or work permit is cancelled, he may claim reimbursement of his direct financial losses caused by the loss of working time up to the time his labour and plant are employed on other work, but not exceeding the period of the cancelled occupation or work permit.
- 5.7 When the Confractor is notified less than 2 hours before the scheduled starting time, or during an occupation or work permit, that the duration of the occupation or work permit is reduced, he may claim reimbursement of his direct financial losses caused by the loss of working time due to the reduced duration of the occupation or work permit.
- Reimbursement of the Contractor for any loss of working time in terms of clause 5.6 and 5.7, shall be subject to his claims being submitted within 14 days of the event with full details of labour and plant involved, and provided that the Contract Supervisor certifies that no other work on which the labour and plant could be employed was immediately available.
- Before starting any work for which an occupation has been arranged, the Contractor shall obtain from the Contract Supervisor written confirmation of the date, time and duration of the occupation
- 5.10 Before starting any work for which a work permit has been arranged, the Responsible Representative shall read and sign portion C of the Work Permit, signifying that he is aware of the work boundaries within which work may be undertaken. After the work for which the permit was granted has been completed, or when the

work permit is due to be terminated, or if the permit is cancelled after the start, the same person who signed portion C shall sign portion D of the Work Permit, thereby acknowledging that he is aware that the electrical equipment is to be made "live". The Contractor shall advise all his workmen accordingly.

#### 6.0 SPEED RESTRICTIONS AND PROTECTION

- 6.1 When speed restrictions are imposed by the network operator because of the Contractor's activities, the Contractor shall organise and carry out his work so as to permit the removal of the restrictions as soon as possible.
- 6.2 When the Contract Supervisor considers protection to be necessary the Contractor shall, unless otherwise agreed, provide all protection including flagmen, other personnel and all equipment for the protection of the network operator's and the Contractor's personnel and assets, the public and including trains.
- 6.2.1 The network operator will provide training free of charge of the Contractor's flagmen and other personnel performing protection duties. The Contractor shall consult with the Contract Supervisor, whenever he considers that protection will be necessary, taking into account the minimum permissible clearances set out in the Manual for Track Maintenance (Document no. BBB0481):
  - Drawing no. BE-97 Sheet 1. Horizontal Clearances: 1065mm gauge (Annexure 1 sheet 1,
  - Drawing no. BE-97 Sheet 2: Vertical Clearances: 1065mm gauge (Annexure 1 sheet 2)
  - Drawing no. BE-97 Sheet 3; Clearances: Platform (Annexure 1 sheet 3)
  - Drawing no. BE-97 Sheet 6: Clearances: 610mm Gauge (Annexure 1 sheet 5)
- 6.3 The Contractor shall appoint a Responsible Representative to receive and transmit any instruction which may be given by the network operator personnel providing projection.

#### 7.0 ROADS AND ROADS ON THE NETWORK OPERATOR'S PROPERTY

- 7.1 The Contractor shall take every reasonable precaution to prevent damage to any roads or bridges used to obtain access to the site, and shall select routes, use vehicles, and restrict loads so that any extraordinary traffic as may arise from the moving of plant or material to or from the site shall be limited as far as is reasonably possible.
- 7.2 The Contractor shall not occupy or interfere in any way with the free use of any public or private road, right-of-way, path or street unless the Contract Supervisor has obtained the approval of the road authority concerned.

#### 8.0 CLEARANCES

- 8.1 No temporary works shall encroach on the appropriate minimum clearances set out in the Manual for Track Maintenance (Document no. BBB0481):
  - Drawing no BE-97 Sheet 1: Horizontal Clearances: 1065mm gauge (Annexure 1 sheet 1)
  - Drawing to BE-97 Sheet 2: Vertical Clearances: 1065mm gauge (Annexure 1 sheet 2).
  - Drawing no. BE-97 Sheet 3: Clearances: Platform (Annexure 1 sheet 3)
  - Drawing no. BE-97 Sheet 5: Clearances: 610mm Gauge (Annexure 1 sheet 5)

#### 9.0 STACKING OF MATERIAL

9.1 The Contractor shall not stack any material closer than 3m from the centre line of any railway line without prior approval of the Contract Supervisor.

#### 10.0 EXCAVATION, SHORING, DEWATERING AND DRAINAGE

10.1 Unless otherwise approved by the Contract Supervisor any excevation adjacent to a railway line shall not encroach on the hatched area shown in Figure 1.



- 10.2 The Contractor shall provide, at his own cost any shoring, deviationly or drainage of any excavation unless otherwise supulated elsewhere in the Contract.
- 10.3 Where required by the Contract Supervisor, drawings of shoring for any excavation under or adjacent to a railway fine shall be submitted and permission to proceed obtained before the excavation is commenced.
- 10.4 The Contractor shall prevent ingress of water to the excevation but where water does enter he shall dispose of it as directed by the Contract Supervisor.
- 10.5 The Contractor shall not block, obstruct or damage any existing drains either above or below ground level unless he has made@dequate prior arrangements to deal with drainage.

#### 11.0 FALSEWORK FOR STRUCTURES

- Drawings of falsework for the construction of any structure over, under or adjacent to any railway line shall be submitted to the Contract Supervisor and his permission to proceed obtained before the falsework is erected. Each drawing shall be given a title and a distinguishing number and shall be signed by a registered professional engineer certifying that he has checked the design of the falsework and that the drawings are correct and in accordance with the design.
- After the falsework has been erected and before any load is applied, the Contractor shall submit to the Contract Supervisor a certificate signed by a registered professional engineer certifying that he has checked the falsework and that it has been erected in accordance with the drawings. Titles and numbers of the drawings shall be stated in the certificate. Notwithstanding permission given by the Contract Supervisor to proceed, the Contractor shall be entirely responsible for the safety and adequacy of the falsework.

#### 12.0 PILING

12.1 The Contract Supervisor will specify the conditions under which siles may be installed on the network operator's property.

#### 13.0 UNDERGROUND SERVICES

- 13.1 No pegs or stakes shall be driven or any excavation made before the Contractor has established that there are no underground services which may be damaged thereby.
- Any damage shall be reported immediately to the Contract Supervisor, or to the official in charge at the nearest station, or to the traffic controller in the case of centralised traffic control.

#### 14.0 BLASTING AND USE OF EXPLOSIVES

- When blasting within 500m of a railway line, the Contractor shall observe the requirements stipulated in this specification.
- 14.2 No blasting shall be carried out except with the prior written permission of the Contract Supervisor and under such conditions as he may impose.
- On electrical Officer (Contractor shall also obtain the permission of the Electrical Officer (Contracts) before blasting, and shall give at least 21 days notice of his intention to blast. No blasting shall be done in the vicinity of electrified lines unless a member of the network operator's electrical personnel is present
- 14.4 The Contractor shall arrange for the supply, transport storage and use of explosives.
- The Contractor shall have labour, tools and plant, to the satisfaction of the Contract Supervisor, available on the site to clear immediately any stones or debris deposited on the track or formation by blasting, and to repair any damage to the track or formation immediately after blasting. Repairs to the track shall be carried out only under the supervision of a duly authorised representative of the network operator.
- 14.6 The Contractor shall notify the Contract Supervisor of his intention to blast at least 21 days before the commencement of any blasting operations.
- Before any blasting is undertaken, the Contractor and the Contract Supervisor shall jointly examine and measure up any buildings, houses or structures in the vicinity of the proposed blasting to establish the extent of any existing cracking or damage to such structures, etc. The Contractor, shall, subject to the provisions stipulated in the Contract Insurance Policy, make good any deterioration of such buildings, houses, or structures, which, in the opinion of the Contract Supervisor, was directly caused by the blasting.
- 14.6 After completion of the blasting the Contractor shall obtain a written clearance from each landowner in

- the vicinity of the blesting operations to the effect that all claims for compensation in respect of damage caused by the blasting operations to their respective properties, have been settled.
- 14.9 The Contractor shall provide proof that be has complied with the provisions of clauses 10.17.1 to 10.17.4 of the Explosives Regulations (Act 26 of 1956 as amended).
- Blasting within 500m of a railway line will only be permitted during intervals between trains. A person appointed by the Contract Supervisor, assisted by flagmen with the necessary protective equipment, will be in communication with the controlling railway station.
  - Only this person will be authorised to give the Contractor permission to blast, and the Contractor shall obey his instructions implicitly regarding the time during which blasting may take place.
- The flagmen described in clause14.10, where provided by the network operator, are for the protection of trains and the network operator's property only, and their presence does not relieve the Contractor in any manner of his responsibilities in terms of Explosives Act or Regulations, or any obligation in terms of this Contract.
- 14.12 The person described in clause 14.10 will record in a book provided and retained by the network operator, the dates and times:
  - (i) when each request is made by him to the controlling station for permission to blast,
  - (ii) when blasting may take place:
  - (iii) when blasting actually takes place, and
  - (iv) when he advises the controlling station that the line is safe for the passage of trains
- 14.16 Before each blast the Contractor shall record in the same book, the details of the blast to be carried out. The person appointed by the Contract Supervisor and the person who will do the blasting shall both sign the book whenever an entry described in clause 14.12 is made.

#### 15.0 RAIL TROLLEYS

- 15.1 The use of rail trolleys or trestle trolleys on a railway line for working on high voltage equipment will be permitted only if approved by the Contract Supervisor and under the conditions stipulated by him.
- 15.2 All costs in connection with trolley working and any train protection services requested by the Contractor shall, be borne by the Contractor unless otherwise agreed.

#### 16.0 SIGNAL TRACK CIRCUITS

- 16.1 Where signal track chooses are installed, the Contractor shall ensure that no material capable of conducting an electrical current makes contact between ralls of railway line/lines.
- 16.2 No signal connections on track-circuited tracks shall be severed without the Contract Supervisor's knowledge and consent.

#### 17.0 PENALTY FOR DELAYS TO TRAINS

17.1 If any trains are delayed by the Contractor and the Contract Supervisor is satisfied that the delay was avoidable, a penalty will be imposed on the Contractor as stipulated in the contract, for the period and number of trains delayed.

#### 18.0 SURVEY BEACONS AND PEGS

- 18.1 The Contractor shall not on any account move or damage any beacon, bench mark, reference mark, signal or trigonometrical station in the execution of the Works without the written approval of the Contract Supervisor.
  - Should the Contractor be responsible for any such occurrence, he shall report the circumstances to the Contract Supervisor who will arrange with the Director-General of Surveys for replacement of the beacon or mark at the cost of the Contractor.
- The Contractor shall not move or damage any cadastration mining beacon without the written approval of the Contract Supervisor and before it has been referenced by a registered land surveyor. Any old boundary beacon, which becomes an internal beacon on creation of new boundaries, shall not be moved without the written approval of the Contract Supervisor.

- Should the Contractor move or damage any cadastral or mining peacon without authority, he shall be responsible for having it replaced, at his cost, by a land surveyor.
- 18.3 The Contractor shall preserve all pags and bench marks. Such survey points shall not be removed without the written approval of the Contract Supervisor. Should any pag or benchmark be removed without authority, the Contract Supervisor will arrange for its replacement and the cost will be recovered from the Contractor. No claim will be considered for delay in replacing any such pag or bench mark. Each pag replaced shall be checked by the Contractor.
- Where a new boundary has been established, beacons on the fence line shall not be disturbed, and fence posts or anchors may not be placed or excavations made within 0.6 m of any beacon without the prior written approval of the Contract Supervisor

#### 19.0 TEMPORARY LEVEL CROSSINGS

- The Contract Supervisor may, on request of the Contractor, and if necessary for the purpose of execution of the Works, permit the construction of a temporary level crossing over a railway a line at a position approved by the Contract Supervisor and at the Contractor's cost. The period for which the temporary level crossing is permitted will be at the discretion of the Contract Supervisor.
- 19.2 The Contractor will provide protection and supervise the construction of the road over the track(s) and within the railway servitude at the level crossing, as well as the erection of all road signs and height gauges. All cost to be borne by the applicant.

The Contractor shall exercise extreme caution in carrying out this work, especially in respect of damage to tracks, services, overhead power and communications routes and prevent contact with "live" overhead electrical equipment.

Unless otherwise agreed, the Contractor will provide the service deviations or afterations to the network operator's track-, structure-, drainage-, electrical-, telecommunications- and train authorisation systems to accommodate the level crossing.

- The Contractor shall take all necessary steps including the provision of gates, locks and, where necessary, watchmen to restrict the use of the temporary level crossing to himself and his employees, his subcontractors and their employees, the staff of the network operator and to such other persons as the Contract Supervisor may permit and of whose identity the Contractor will be advised. If so ordered by the Contract Supervisor, the Contractor shall provide persons to control road traffic using the temporary level crossing. Such persons shall stop all road traffic when any approaching train is within seven hundred and fifty (750) metres of the temporary level crossing, and shall not allow road traffic to proceed over it until the lines are clear.
- 19.4 The Contractor shall maintain the temporary level crossing within the railway servitude in good condition for the period it is in use. A temporary agreement with the road authority to be concluded for the maintenance of the level crossing outside the railway servitude.
- When the temporary level crossing is no longer required by the Contractor, or permitted by the network operator, the Contractor shall at his own cost remove it and restore the site and the network operator's track-, structure-, drainage-, electrical-, telecommunications- and train authorisation systems to its original condition. Work over the tracks and within the railway servitude will be supervised by the network operator.

#### 20.0 COMPLETION OF THE WORKS

20.1 On completion of the works, the Contractor shall remove all the remaining construction plant and material from the site, other then material which is the property of the network operator, and leave the site in a clean, neat and fidy condition, if material and plant is required for the liability and maintenance period the Contract supervisor must authorise it's retention on site.

### 21.0 PROTECTION OF PERSONS AND PROPERTY

21.1 The Contractor shall provide and maintain all lights, guards, barriers, fencing and watchmen when and where necessary or as required by the Contract Supervisor or by any statutory authority, for the profection of the Works and for the safety and convenience of the public.

Red, yellow, green or blue lights may not be used by the Contractor as they can be mistaken for signals Red, yellow, green or white flags shall only be used for protection by the Contractor. Within the precincts of a port the Contractor shall obtain the permission of the Port Captain before installing any light.

- 21.2 The Contractor shall take all the requisite measures and procautions during the course of the Works to:
  - (t) protect the public and property of the public,
  - (ii) protect the property and workmen of both the network operator and the Contractor,
  - (iii) avoid damage to and prevent trespass on adjoining properties, and
  - (iv) ensure compliance with any instruction issued by the Contract Supervisor or other authorised person and with any stipulation embodied in the contract documents which affects the safety of any person or thing.
- 21.3 The network operator will provide, at its own cost, protection for the safe working of trains during such operations as the Contract Supervisor may consider necessary. Protection by the network operator for any purpose whatsoever, does not absolve the Contractor of his responsibilities in terms of the Contract.
- 21.4 The Contractor shall take all precautions and appoint guards, watchmen and compound managers for prevention of disorder among and misconduct by the persons employed on the Works and by any other persons, whether employees or not, on the work site and for the preservation of the peace and protection of persons and property in the direct neighbourhood. Any relocation of camps because of disorder shall be at the Contractor's expense.
- All operations necessary for the execution of the Works, including the provision of any temporary work and camping sites, shall be carried out so as not to cause veldt fires, ground and environmental pollution, soil erosion or restriction of or interference with streams, furrows, drains and water supplies.
  - if the original surface of the ground is disturbed in connection with the Works, it shall be made good by the Contractor to the satisfaction of the land owner, occupier or responsible authority
- 21.6 The Contractor shall take all reasonable steps to minimise noise and disturbance when carrying out the Works, including work permitted outside normal working hours.
- 21.7 Durnping of waste or excess materials by the Contractor shall, in urban areas, be done under the direction and control of, and at sites made available by the local authority. Dumping outside local authority boundaries shall be done only with the express permission and under the direction and control of the Contract Supervisor.
- 21.8 The Contractor shall comply with environmental protection measures and specifications stipulated by the Contract Supervisor and/or local and environmental authorities.

## 22.0 INTERFERENCE WITH THE NETWORK OPERATOR'S ASSETS AND WORK ON OPEN LINES

- 22.1 The Contractor shall not interfere in any manner whatsoever with an open line, nor shall be carry out any work or perform any act which affects the security, use or safety of an open line except with the authority of the Contract Supervisor and in the presence of a duty authorised representative of the network operator.
- 22.2 The Contractor shall not carry out any work or operate any plant, or place any malerial whatsoever nearer than three metres from the centre line of any open line except with the written permission of the Contract Supervisor and subject to such conditions as he may impose.
- Care must be taken not to interfere with or damage any services such as overhead wire routes, cables or pipes and optical fibre cable, except as provided for the work specified. The Contractor will be held responsible for any damage to or interruption of such services arising from any act or omission on his part or of any of his employees, or persons engaged by him on the Works. The cost of repairing, replacing or restoring the services, as well as all other costs arising from any damage to services, shall be borne by, and will be recovered from the Contractor.
- Authority granted by the Contract Supervisor and the presence of an authorised representative of the network operator in terms hereof, shall not relieve the Contractor of his duty to comply with this specification.
- 23.0 ACCESS, RIGHTS-OF-WAY AND CAMPSITES
- 23.1 Where entry onto the network operator's property is restricted, permission to enter will be given only for the purpose of carrying out the Works and will be subject to the terms and conditions laid down by the network operator.
- 23.2 The Contractor shall arrange for campsites, workplaces and access thereto as well as for any right-of-

way over private property to the site of the Works, and for access within the boundaries of the network operators property. The owners of private property to be traversed shall be approached and treated with tact and courtesy by the Contractor, who shall, if necessary, obtain a letter of introduction to such property owners from the Contract Supervisor.

The Contractor shall be responsible for the closing of all gates on roads and tracks used by him or his employees. Except with the prior approval of the Contract Supervisor and the owner or occupier of any private land to be traversed, the Contractor shall not cut, lower, damage, remove or otherwise interfere with any fence or gate which is either on the network operator's property or on private property and which restricts access to the Works. Where such approval has been given, the Contractor shall prevent entry of animals or unauthorised persons onto the network operator's or private property, and shall make the fences safe against trespass at the close of each day's work.

- 23.3 The Contractor shall take all reasonable steps to confine the movement of vehicles and plant to the approved right-of-way to minimise damage to property, crops and natural vegetation
- When access is no longer required, and before completion of the Works, the Contractor shall repair, restore or replace any fence or gate damaged during execution of the Works to the satisfaction of the Contract Supervisor and shall furnish the Contract Supervisor with a certificate signed by the owner and occupier of land over which he has gained access to a campsite, workplace and the Works, certifying that the owner and occupier have no claim against the Contractor or the network operator arising from the Contractor's use of the land. Should the Contractor be unable to obtain the required certificate, he shall report the circumstances to the Contract Supervisor.

#### 24.0 SUPERVISION

- 24.1 The Contract Supervisor will provide overall technical superintendence of the Works, and may direct the Contractor in terms of the provisions of the Contract or in tespect of any measures which the Contract Supervisor may require for the operations of the network operator, the safety of trains, properly and workmen of the network operator, and for the safety of other properly and persons. The Contractor shall carry out the directions of the Contract Supervisor. The superintendence exercised by the Contract Supervisor, including any agreement, approved, refusal or withdrawal of any approval given, shall not relieve the Contractor of any of his duties and liabilities under the Contract, and shall not imply any assumption by the network operator or by the Contract Supervisor of the legal and other responsibilities of the Contractor in carrying out the Works.
- The Contract Supervisor may delegate to any deputy or other person, any of his duties or functions under the Contract. On receiving notice in writing of such delegation, the Contractor shall recognise and obey the deputy or person to whom any such duties or functions have been delegated as if he were the Contract Supervisor.
- 24.3 The Contractor shall exercise supervision over the Works at all times when work is performed or shall be represented by an agent having full power and authority to act on behalf of the Contractor. Such agent shall be competent and responsible, and have adequate experience in carrying out work of a similar nature to the Works, and shalt exercise personal supervision on behalf of the Contractor. The Contract Supervisor shall be notified in writing of such appointment which will be subject to his approval.
- 24.4 The Contractor or his duly authorised agent shall be available on the site at all times while the Works are in progress to receive the orders and directions of the Contract Supervisor

#### 25.0 HOUSING OF EMPLOYEES

- The Contractor shall, where necessary, make his own arrangements for suitable housing of his employees. Where temporary housing is permitted by the Contract Supervisor on any part of the site, the Contractor shall provide suitable sanitation, lighting and potable water supplies in terms of the requirements of the local authority or the current network operator's specification; Minimum Communal Health Requirements in Areas outside the Junisdiction of a Local Authority £ 48, as applicable
- 25.2 Fouling the area inside or outside the network operator's boundaries shall be prevented. The Contractor will be called upon by the Contract Supervisor to dispose of any foul or waste matter generated by the Contractor

#### 26.0 OPTICAL FIBRE CABLE ROUTES

- 26.1 The Contractor shall not handle, impact, move or deviate any optical fibre cable without prior approval.
- 26.2 Works that in any way affect the optical fibre cable requires prior approval from the Contract Supervisor

who will determine the work method and procedures to be followed.

oreview copy only

## PART B - SPECIFICATION FOR WORK NEAR HIGH-VOLTAGE ELECTRICAL EQUIPMENT

#### 27.0 GENERAL

- 27.1 This specification is based on the contents of Transnet's publication ELECTRICAL SAFETY INSTRUCTIONS, as amended, a copy of which will be made available on loan to the Contractor for the duration of the contract
  - These instructions apply to all work near "live" high-voltage equipment maintained and/or operated by the network operator, and the onus rests on the Contractor to ensure that he obtains a copy.
- 27.2 This specification must be read in conjunction with and not in lieu of the Electrical Safety Instructions
- 27.3 The Contractor's attention is drawn in particular to the contents of Part I. Sections 1 and 2 of the Electrical Safety Instructions
- 27.4 The Electrical Safety Instructions cover the minimum safety precautions which must be taken to ensure safe working on or near night-voltage electrical equipment, and must be observed at all times. Should additional safety measures be considered necessary because of peculiar local conditions, these may be ordered by and at the discretion of the Electrical Officer (Contracts).
- 27.5 The Contractor shall obtain the approval of the Electrical Officer (Contracts) before any work is done which causes or could cause any portion of a person's body or the tools he is using or any equipment he is handling, to come within 3 metres of any "live" high-voltage equipment.
- 27.6 The Contractor shall regard all high-voltage equipment as "live" unless a ward permit is in force.
- 27.7 Safety precautions taken or barriers erected shall comply with the requirements of the Electrical Officer (Contracts), and shall be approved by him before the work to be protected is undensken by the Contractor. The Contractor shall unless otherwise agreed, bear the cost of the provision of the barriers and other safety precautions required, including the attendance of the betwork operator's staff where this is necessary.
- 27.8 No barrier shall be removed unless authorised by the Electrical Officer (Contracts).

## 28.0 WORK ON BUILDINGS OR FIXED STRUCTURES

- 28.1 Before any work is carried out or measurements are taken on any part of a building, fixed structure or earthworks of any kind above ground level situated within 3 metres of "live" high-voltage equipment, the Electrical Officer (Contracts) shall be consulted to ascertain the conditions under which the work may be carried out.
- 28.2 No barrier erected to comply with the requirements of the Electrical Officer (Contracts) shall be used as temporary staging or shultering for any part of the Works.
- 28.3 The shuttering for bridge piers, abutments, retaining walls or parapets adjacent to or over any track may be permitted to serve as a barrier, provided that it extends at least 2,5 metres above any working level in the case of pers, abutments and retaining walls and 1,5 metres above any working level in the case of parapets.

## 29.0 WORK DONE ON OR OUTSIDE OF ROLLING STOCK, INCLUDING LOADING OR UNLOADING

- 29.1 No person may stand, climb or work, whilst on any platform, surface or footbold:
- 29.1.1 higher than the normal unrestricted access way, namely -
- 29 1.1.1 external walkways on diesel, steam and electric locomotives, steam heat vans, etc. and
- 29.1-1.2 walkways between coaches and locomotives
- 29.1.2 of restricted access ways in terms of the Electrical Safety Instructions namely -
- 29 1 2 1 the floor level of open wagons
- 29.1.2.2 external walkways or decks of road-rail vehicles, on-frack maintenance machines and material trains.
- 29.1.3 Unauthorised staff working on these platforms must be directly supervised by duly authorised persons in terms of clause 607.1.3 of the Electrical Safety Instructions. These persons must attend the relevant electrical safety module training. A retter of training must then be issued by an accredited training authority. A Category C Certificate of Authority must be obtained from the

local depot examining efficer.

- 29.2 When in the above positions no person may raise his hands or any equipment he is handling above his head
- 29.3 In cases where the Contractor operates his own rall mounted equipment, he shall arrange for the walkways on this plant to be inspected by the Electrical Officer (Contracts) and approved, before commencement of work
- 29.4 The handling of long tengths of material such as metal pipes, reinforcing bars, etc should be avoided, but if essential they shall be handled as nearly as possible in a horizontal position below head height.
- 29.5 The Responsible Representative shall warn all persons under his control of the danger of being near "live" high-voltage equipment, and shall ensure that the warning is fully understood.
- 29.6 Where the conditions in clauses 30.1 to 30.4 cannot be observed the Electrical Officer (Contracts), shall be notified. He will arrange for suitable Safety measures to be taken. The Electrical Officer (Contracts), may in his discretion and in appropriate circumstances, arrange for a suitable employee of the Contractor to be specially trained by the network operator and at the Contractor's cost, as an Authorised Person to work closer than 3 metres from "live" overhead conductors and under such conditions as may be imposed by the senior responsible electrical engineer of the network operator.

#### 30.0 USE OF EQUIPMENT

- 30.1 Measuring Tapes and Devices
- 30.1.1 Measuring tapes may be used near "live" high-voltage equipment provided that no part of any tape or a person's body comes within 3 metres of the "live" equipment.
- 30.1.2 In windy conditions the distance shall be increased to ensure that if the tape should fall it will not be blown nearer than 3 metres from the "live" high-voltage equipment.
- 30.1.3 Special measuring devices longer than 2 metres such as survey sticks and rods may be used if these are of non-conducting material and approved by the responsible Electrical Engineer of the network operator, but these devices must not be used within 3 metres of "live" high-voltage equipment in rainy or wet conditions.
- 30.1.4 The assistance of the Electrical Officer (Contracts) shall be requested when measurements within the limits defined in clauses 31.1.1 to 31.1.8 are required.
- 30.1.5 The restrictions described in 31.11 to 31.1.3 do not apply on a bridge deck between permanent parapets nor in other situations where a barrier effectively prevents contact with the "live" high-voltage equipment.
- 30.2 Portable Ladders
- 30.2.1 Any type of portable ladder longer then 2 metres may only be used near "tive" high-voltage equipment under the direct supervision of the Responsible Representative. He shall ensure that the ladder is always used in such a manner that the distance from the base of the ladder to any "live" high-voltage equipment is greater than the fully extended length of the ladder plus 3 metres. Where these conditions cannot be observed, the Electrical Officer (Contracts) shall be advised, and he will arrange for suitable safety measures to be taken
- 31.0 CARRYING AND HANDLING MATERIAL AND EQUIPMENT
- Pipes, scaffolding, non-sheets, reinforcing bars and other material which exceeds 2 metres in length shall be carried completely below head height near "live" high-voltage equipment. For maximum safety such material should be carried by two or more persons so as to maintain it as nearly as possible in a horizontal position. The utmost care must be taken to ensure that no part of the material comes within 3 metres of any "live" high-voltage equipment.
- 31.2 Long lengths of wire or cable shall never be run out in conditions where a part of a wire or cable can come within 3 metres of any five" high-voltage equipment unless the Electrical Officer (Contracts) has been advised and has approved appropriate safety precautions.
- 31.3 The presence of overhead power lines shall always be taken account of especially when communications lines or cables or aerial cables, stay wires, etc. are being erected above ground level.
- 32.0 PRECAUTIONS TO BE TAKEN WHEN ERECTING OR REMOVING POLES, ANTENNAE, TREES ETC.
- 32.1 A pote may be handled for the purpose of erection or removal near high-voltage equipment under the following conditions

- (i) If the distance between the point at which the pole is to be erected or removed and the nearest live' high-voltage equipment is more than the length of the pole plus 3 metres, the work shall be supervised by the Responsible Representative
- (ii) If the distance described in (i) is less than the length of the pole plus 3 metres, the Electrical Officer (Contracts) shall be consulted to arrange for an Authorised Person to supervise the work and to ensure that the pole is earthed where possible. The pole shall be kept in contact with the point of erection and adequate precautions shall be taken to prevent contact with "live" nigh-voltage equipment.
- 32.2 The cost of supervision by an Authorised Person and the provision of earthing shall, unless otherwise agreed, be borne by the Contractor.
- 32.3 The provisions of clauses 33.1 and 33.2 shall also apply to the erection or removal of columns, antennae trees, posts, etc.
- 33.0 USE OF WATER
- 33.1 No water shall be used in the form of a jet if it can make contact with any "live" high-voltage equipment or with any person working on such equipment.
- 34.0 USE OF CONSTRUCTION PLANT
- 34.1 "Construction plant" entails all types of plant including cranes, piling frames, boring machines, excavators dragtines, dewatering equipment and road vehicles with or without lifting equipment.
- 24.2 When work is being undertaken in such a position that it is possible for construction plant or its load to come within 3 metres of "live" high-voltage equipment, the Electrical Officer (Confidence) shall be consulted. He will arrange for an Authorised Person to supervise the work and to chaure that the plant is adequately earthed. The Electrical Officer (Contracts) will decide whether further sefety measures are necessary.
- 34.3 The cost of any supervision by an Authorised Person and the provision of earthing shall, unless otherwise agreed, be borne by the Contractor
- When loads are handled by cranes, non-metallic tope hand lines shall be used, affixed to such loads so as to prevent their swinging and coming within 3 metres of "live" high-voltage equipment.
- 34.5 Clauses 35.1 to 35.4 shall apply mutatis mutandis to the use of maintenance machines of any nature.
- 35.0 WORK PERFORMED UNDER DEAD CONDITIONS UNDER COVER OF A WORK PERMIT
- 35.1 If the Responsible Representative finds that the work cannot be done in safety with the high-voltage electrical equipment "live", he shall consult the Electrical Officer (Contracts) who will decide on the action to be taken.
- 35.2 If a work permit is ssued the Responsible Representative shall-
  - (i) before commencement of work ensure that the limits within which work may be carned out have been explained to him by the Authorised Person who issued the permit to him, and that he fully understands these limits
  - (ii) sign portion C of the permit before commencement of work.
  - (iii) explain to all persons under his control the limits within which work may be carned out, and ensure that they fully understand these limits:
  - (iv) care for the safety of all persons under his control whilst work is in progress; and
  - (v) withdraw all personnel under his control from the equipment on completion of the work before he signs pontion D of the work permit
- 36.0 TRACTION RETURN CIRCUITS IN RAILS
- 36.1 DANGEROUS CONDITIONS CAN BE CREATED BY REMOVING OR SEVERING ANY BOND
- 36.2 Broken rails with an air gap between the ends, and joints at which fishplates are removed under "broken bond" conditions, are potentially lethal. The rails on either side of an air gap between rail ends on electrified lines shall not be touched simultaneously until rendered safe by the network operator personnel.
- 36.3 The Contractor shall not break any permanent bonds between rails or between rails and any structure. He shall give the Contract Supervisor at least 7 days written notice when removal of such bonds is necessary.

No work on the track which involves interference with the traction return rail circuit either by culting or removing the rails, or by removal of bonds shall be done unless the Electrical Officer (Contracts) is 36.4 consulted. He will take such precautions as may be necessary to ensure continuity of the return circuit pefore permitting the work to be commenced.

#### HIGH-VOLTAGE ELECTRICAL EQUIPMENT NOT MAINTAINED AND/OR OPERATED BY THE 37.0 NETWORK OPERATOR

Where the work is undertaken on or near high-voltage electrical equipment which is not maintained and/or operated by the network operator, the Occupational Health and Safety Act No. 85 of 1993, and Regulations and Instructions, or the Mines Health and Safety Act (Act 29 of 1996), shall apply.

Such equipment includes.-

- (i) Eskom and municipal equipment
- (ii) The Contractor's own power supplies; and
- (iii) Electrical equipment being installed but not yet taken over from the Contractor.

FND

oreview copy only

## HORIZONTAL CLEARANCES 065mm TRACK GAUGE

ANNEXURE 1 SHEET 1 01 5



MAY BE REDUCED BY SOFTH MATERIAL DATES MAY 90 INTERPOLATED BY THE ENGINEER IN CHARGE. AND FOR WORKSHOP AREAS AND TEMPORARY WORK, CLEARANCES

IS THE REDURACE HORIZONTAL CLEARANCE ON THE LOW LEG OF THE CURVE RASED ON MAXIBLIAN CANT.

@ SEE ANNUXURE : SHEET 3 FOR PLATFORM CLEARANCES.

ALSO REFER TO REWARKS A TO 8 OF ANNEXURE 1 SHEET SAMULER RADIUS IF RADIUS INSTITUTES 983

S ONV 1

ANNEXURE 1 SHEET 2 of 5

## VERTICAL CLEARANCES : 1 065mm TRACK GAUGE

ELECTRIFIED  ESENT OR FULUED  ESENT OR FULUED	50%×	. č		012		4 990 S 340 WORKSHOP AREAS AND			082 \$ 280	5 650 6 000 RAIL (EVEL-10) LES
186	38V & 25kV 50K		K')	υ) 	(C)	(1')	45 C90	<u>(2)</u>	S 000	9
100 NOT	L.1. 9 8 9	(2002)	5 470 E	0.8	0 6	() () () ()	(7)	062 v	200	OVER OR NEAR FOUNTS AND DROSSING IF REQUIRED BY ELECTRICAL RRESPECTIVE OF RADRITS
	7.	820028 (mm)	85:	8	609	8	000	300 3	000 57	ONER OF NEAR AND DROSS NO F BY ELECTRICAL

KONT CHEKETOETS V 13 THE PECUNIED VERNICAL CLEARANCE EXCEPT WHERE REDUCED CLEARANCE & APPLIES S IS THE MINNAUN VERTICAL CLEARANCE FOR STRUCTURES AND TEMPORARY WORK OVER RESIMENS

3. MILEMEDIATE VALUES MAY BE MITTAPOLATED BY THE ENGINEER IN CHARGE.

A 10R APRICATION AT CURVES

A,S FOR NON-TRAMSHIGMED CURVES REDUCE AT A UNIFORM RATE DYER A LENGTH OF 15m A,074G STRAIGHTS. ALL ASPLY BACHEASED CLEARANCES FOR CURVES TO POINTS 3m BEYOND THE EMDS OF THE CIRCLE 4.2 REDINCE CLEARANCES AT A UNIFORM RATE OVER THE REMAINDER OF THE TRANSITION CURVE.

3, NEW STRUCTURES, SEC BRYDOS, CODE.


e, Turnelle See Drawing BF 52 - 35

T. FOULMO FORM'S. SEE CLAUSE 8.1.

S. CLEARAWCES ARE BASED ON 15m BOOIE CENTRES AND 21,2m VECHILE BODY LENGTH.

CLEARANCES : PLATFORMS

ANNEXURE 1 SHEET 3 of 5



STRUCTURES ON PLATFORMS: 1 065mm AND 610mm TRACK GAUGE



CLEARANCES : 610mm TRACK GAUGE

ANNEXURE 1 SHEET 5 of 5

